

- 1. Existing Home
- 2. Pond Edge
- 3. 25' Natural Features Setback
- 4. 50' Septic Field Setback
 5. Vegetative Buffer, planted with native grasses shrubs
 6. Potential Locations for Septic Fields and Reserve Areas
- 7. Renovated Studio Building
- 8. Proposed Canopy Tree, Typical (see legend for possible palette)

- 9. Existing Canopy Tree, Typical
 10. Existing Evergreen Tree, Typical
 11. Proposed Ornamental Trees (see legend for possible palette)
 12. Proposed Evergreen Trees (see legend for possible palette)
- 13. Stone Overlook
- 14. Pavilion Structure with Decorative Paving
- 15. Deciduous Evergreen Shrub masses with Ground Cover
- 16. Sitting Area adjacent to Water Feature 17. Water Feature "Babbling Brook"
- 18. Walking Path of Permeable Material, Typical 19. Main Terrace of Decorative Paving with Cut Outs for Planting
- 20. Existing Entry Trellis
- 21. Enhanced Drop Off with Low Stone Wall 22. Feature in Raised Planting Bed (TBD)
- 23. Low Bollards with Low-Volt Lighting to Define Driveway
- 24. Layered Plantings to Define Meadow Edge 25. Lawn Meadow with Seasonal Color
- 26. Lighted Entry Piers and Timber Gates
- 27. Lawn, Typical

Existing/Proposed Tree Quantity Summary

Existing Tree On-Site Prior to Construction: 151

Proposed Summary from May 10, 2012 HDC Meeting

Total Trees to be Removed: 78 Total Trees to Remain: 73

Total Trees to be Planted: 189 Total Existing and Proposed Trees on Site: 262

Proposed Summary This Submittal; January 21, 2013:

Total Trees to be Removed: 84 Total Trees to Remain: 67 Total Trees to be Planted: 157

Possible Tree Palette Legend

Total Existing and Proposed Trees on Site: 224




River Birch Red Oak



Evergreen Tree

White Spruce Norway Spruce Douglas Fir White Pine



Eastern Red Bud

Washington Residence

Rochester Hills, Michigan

Landscape Master Plan January 21, 2013

