


HRC
HUBBELL, ROTH & CLARK, INC
 CONSULTING ENGINEERS SINCE 1915
 555 HULET DRIVE P.O. BOX 824
 BLOOMFIELD HILLS, MICH. 48303-0824
 PHONE: (248) 454-8300
 FAX (1st Floor): (248) 454-8312
 FAX (2nd Floor): (248) 338-2592
 WEB SITE: http://www.hrc-engr.com

DATE	ADDITIONS AND/OR REVISIONS
7-5-17	ISSUED FOR CONSTRUCTION
5-9-17	FINAL PLAN SUBMITTAL
3-1-17	PRELIM. PLAN SUBMITTAL
1-25-17	UTILITY REVIEW
DESIGNED	COB
DRAWN	COB
CHECKED	LFM
APPROVED	



ROCHESTER HILLS
EDDINGTON BOULEVARD
REALIGNMENT

PAVEMENT MARKING AND SIGNING PLAN

HRC JOB NO. 20161000	SCALE 1" = 40'
DATE MARCH 2017	SHEET NO. 32 OF 87

QUANTITIES - THIS SHEET - PARTICIPATING

Description	Total	Unit
Pavt Mrkg, Sprayable Thermopl, 4 inch, White	1185	Ft
Pavt Mrkg, Sprayable Thermopl, 4 inch, Yellow	3250	Ft
Pavt Mrkg, Polyurea, 24 inch Stop Bar	170	Ft
Pavt Mrkg, Polyurea, 6 inch, Crosswalk	470	Ft
Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	8	Ea
Pavt Mrkg, Ovly Cold Plastic, Rt Turn Arrow Sym	4	Ea
Rem Curing Compound, for Longit Mrkg, 4 inch	1000	Ft
Rem Curing Compound, for Longit Mrkg, 6 inch	200	Ft
Rem Curing Compound, for Spec Mrkg	100	Sft