general landscape notes:

WITH LANDSCAPE ARCHITECT.

- 1. LANDSCAPE CONTRACTOR SHALL VISIT THE SITE, INSPECT EXISITING CONDITIONS, REVIEW PROPOSED PLANTINGS AND RELATED WORK, CONTACT THE OWNER AND/OR LANDSCAPE ARCHITECT WITH ANY CONCERNS OR DISCREPANCY BETWEEN THE PLAN, PLANT MATERIAL LIST, AND/OR SITE CONDITIONS.
- 2. NUMERICAL VALUE ON THE LANDSCAPE QUANTITIES SPECIFIED ON THE PLAN TAKE PRECEDENCE OVER GRAPHIC REPRESENTATION. VERIFY ANY CONCERN-DISCREPANCY
- 3. ALL CONSTRUCTION AND PLANT MATERIAL LOCATION TO BE ADJUSTED ON SITE IF NECESSARY.
- 4. ALL SUBSTITUTIONS OR DEVIATIONS FROM THE LANDSCAPE PLAN MUST BE APPROVED BY CITY OF ROCHESTER HILLS AND LANDSCAPE ARCHITECT
- 5. ALL LARGE TREES AND EVERGREENS TO BE STAKED, GUYED AND WRAPPED AS DETAIL SHOWN ON PLAN.
- 6. PLANT BEDS TO BE DRESSED WITH MIN. 3" OF FINELY DOUBLE SHREDDED HARDBARK MULCH. 1. DIG SHRUB PITS I' LARGER THAN SHRUB ROOT BALLS AND TREE PITS 2' LARGER THAN ROOT BALL. BACK FILL WITH ONE PART TOP SOIL AND ONE PART SOIL FROM EXCAVATED PLANTING HOLE.
- 8. REMOVE ALL TWINE, WIRE AND BURLAP FROM TREE AND SHRUB EARTH BALLS, AND FROM
- 9. NATURAL COLOR, FINELY SHREDDED HARDWOOD BARK MULCH REQUIRED FOR ALL PLANTINGS 4" THICK BARK MULCH FOR TREES IN 4' DIA, CIRCLE WITH 3" PULLED AWAY FROM TRUNK. 3" THICK BARK MULCH FOR SHRUBS AND 2" THICK BARK MULCH FOR PERENNIALS.
- 10. PLANT MATERIAL QUALITY & INSTALLATION SHALL BE IN ACCORDANCE WITH THE CURRENT AMERICAN ASSOCIATION OF NURSERYMEN LANDSCAPE STANDARDS.
- II. PROVIDE PEAT SOD FOR ALL NEW AND DISTURBED LAWN AREAS UNLESS NOTED OTHERWISE. 12. ALL PLANTING AREAS TO BE PREPARED WITH APPROPRIATE SOIL MIXTURES AND
- FERTILIZER BEFORE PLANT INSTALLATION.
- 13. PLANT TREES AND SHRUBS GENERALLY NO CLOSER THEN THE FOLLOWING DISTANCES FROM SIDEWALKS, CURBS AND PARKING STALLS:
 - a). SHADE TREES b). ORNAMENTAL AND EVERGREEN TREES

PLANS FOR EXACT LOCATION AND DETAILS.

AF 2

LS 2

QB 3 AC 3

VMK 14

- (CRAB, PINE, SPRUCE, ETC.) c). SHRUBS THAT ARE LESS THAN I FOOT TALL
- AND WIDE AT MATURITY. 14. NO TREES OR EVERGREENS TO BE INSTALLED OVER ANY PROPOSED OR EXISTING UTILITY LINES AS SHOWN ON THE OVERALL LANDSCAPE PLAN. SEE ENGINEERING
- 15. PRIOR TO BEGINNING OF CONSTRUCTION ON ANY WORK, CONTRACTORS SHALL VERIFY LOCATIONS OF ALL ON SITE UTILITIES. GAS, ELECTRIC, TELEPHONE, CABLE TO BE LOCATED BY CONTACTING MISS DIG 1-800-482-7171. ANY DAMAGE OR INTERRUPTION OF SERVICES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR COORDINATE ALL RELATED WORK ACTIVITIES WITH OTHER TRADES AND REPORT ANY UNACCEPTABLE JOB CONDITIONS TO OWNER PRIOR
- 16. ALL LAWN AREAS AND LANDSCAPE BEDS TO BE FULLY IRRIGATED WITH A AUTOMATIC UNDERGROUND SYSTEMS. IRRIGATION SYSTEM TO HAVE SEPARATE ZONES FOR LAWN AREAS, PARKING ISLANDS, AND SHRUB BEDS WITH DIFFERENT CONTROL MOISTURE LEVEL ADJUSTMENT PER ZONE AS REQUIRED.
- 17. UNLESS NOTED OTHERWISE, LANDSCAPE BEDS ADJACENT TO LAWN TO RECIEVE EDGING. EDGING SHALL BE 4" X 1/8" METAL (FINISH BLACK OR GREEN) OR APPROVED EQUAL AND TO BE INSTALLED WITH HORIZONTAL METAL STAKES AT 32" O.C. OR PER MANUFACTERER'S SPECIFICATION.
- 18.ALL LANDSCAPE BEDS ADJACENT AND NEXT TO BUILDING SHALL BE EXCAVATED OF ALL BUILDING MATERIALS AND POOR SOILS A MIN. OF 12" DEPTH. BACK FILL WITH GOOD, MEDIUM TEXTURED PLANTING SOILS. ADD A MIN. 2" OF TOPSOIL OVERFILL TO FINISH GRADE. PROVIDE POSITIVE DRAINAGE.

- 19. WATERING OF ALL PLANTS AND TREES TO BE PROVIDED IMMEDIATELY AND MULCHING WITHIN 24 HOURS AFTER
- 20. ALL TREE PITS TO BE TESTED FOR PROPER DRAINAGE PRIOR TO TREE PLANTING. PROVIDE APPROPRIATE DRAINAGE SYSTEM AS REQUIRED IF THE TREE PIT DOES NOT DRAIN SUFFICIENTLY.
- THE LANDSCAPE CONTRACTOR SHALL GUARANTEE ALL LANDSCAPE PLANT MATERIALS AND IRRIGATION INSTALLATION FOR A PERIOD OF ONE YEAR BEGINNING AFTER THE COMPLETION OF LANDSCAPE INSTALLTION DATE APPROVED BY THE TOWNSHIP/CITY OR LANDSCAPE ARCHITECT. THE CONTRACTOR SHALL REPLACE DURING AND AT THE END OF THE GUARANTEE PERIOD, ANY DEAD OR UNACCEPTABLE PLANTS, AS DETERMINED BY THE TOWNSHIP/CITY OR LANDSCAPE ARCHITECT, WITHOUT COST
- 2. PRIOR TO THE RELEASE OF THE PERFORMANCE BOND, THE CITY OF ROCHESTER HILLS MUST INSPECT ALL LANDSCAPE

landscape maintenance notes:

THE OWNER OF THE PROPERTY SHALL BE RESPONSIBLE FOR ALL MAINTENANCE OF SITE LANDSCAPING, AS FOLLOWS: 1. LANDSCAPE MAINTENANCE PROCEDURES AND FREQUENCIES TO BE FOLLOWED SHALL BE SPECIFIED ON THE LANDSCAPE PLAN, ALONG WITH THE MANNER IN WHICH THE EFFECTIVENESS, HEALTH AND INTENDED FUNCTIONS OF THE VARIOUS

2. LANDSCAPING SHALL BE KEPT IN A NEAT, ORDERLY AND HEALTHY GROWING CONDITION, FREE FROM DEBRIS AND

LANDSCAPE AREAS ON THE SITE WILL BE ENSURED.

3. PRUNING SHALL BE MINIMAL AT THE TIME OF INSTALLATION, ONLY TO REMOVE DEAD OR DISEASED BRANCHES. SUBSEQUENT PRUNING SHALL ASSURE PROPER MATURATION OF PLANTS TO ACHIEVE THEIR APPROVED PURPOSE.

4. ALL DEAD OR DISEASED PLANT MATERIAL SHALL BE REMOVED AND REPLACED WITHIN SIX (6) MONTHS AFTER IT DIES OR IN THE NEXT PLANTING SEASON, WHICHEVER OCCURS FIRST. THE PLANTING SEASON FOR DECIDUOUS PLANTS SHALL BE BETWEEN MARCH I AND JUNE I AND FROM OCTOBER I UNTIL THE PREPARED SOIL BECOMES FROZEN. THE PLANTING SEASON FOR EVERGREEN PLANTS SHALL BE BETWEEN MARCH I AND JUNE I. PLANT MATERIAL INSTALLED TO REPLACE DEAD OR DISEASED MATERIAL SHALL BE AS CLOSE AS PRACTICAL TO THE SIZE OF THE MATERIAL IT IS INTENDED TO REPLACE.

5. THE APPROVED LANDSCAPE PLAN SHALL BE CONSIDERED A PERMANENT RECORD AND INTEGRAL PART OF THE SITE PLAN APPROVAL. UNLESS OTHERWISE APPROVED IN ACCORDANCE WITH THE AFOREMENTIONED PROCEDURES, ANY REVISIONS TO, OR REMOVAL OF, PLANT MATERIALS WILL PLACE THE PARCEL IN NON-CONFORMITY WITH THE APPROVED LANDSCAPE PLAN, AND SHALL BE VIEW AS A VIOLATION OF THIS ORDINANCE AND THE AGREED UPON TERMS OF THE FINAL SITE PLAN APPROVAL.

> DISTURBED R.O.W. LAWN AREAS TO RECEIVE HYDROSEED ON FINISH GRADES, PROVIDE POSITIVE DRAINAGE.


plant material list					
otanical name	common name	size	unit cost	total cost	
LARGE AND SMALL DECIDUOUS TREES					
ACER X FREEMANII 'JEFFERSRED'	AUTUMN BLAZE RED MAPLE	3" BB	\$300	\$600	
ACER R. 'FRANKSRED'	RED SUNSET RED MAPLE	3' BB	\$3 <i>00</i>	\$600	
LIQUIDAMBER STYRACIFLUA	AMERICAN SWEETGUM	3" BB	\$3 <i>0</i> 0	1600	
QUERCUS BI-COLOR	WHITE SWAMP OAK	3" BB	\$3 <i>00</i>	\$9 <i>00</i>	
ABIES CONCOLOR	WHITE FIR	8' BB	\$35Ø	\$1,050	
ABIES CONCOLOR	WHITE FIR	10' BB O	\$400	\$1,200	
PICEA PUNGENS	COLORADO SPRUCE	8' BB	\$35Ø	\$TØØ	
PICEA PUNGENS	COLORADO SPRUCE	10' BB O	\$400	\$400	
DECIDUOUS SHRUBS					
VIBRUNUM X.B. 'MOHAWK'	MOHAWK VIBURNUM	3 1/2' BB	45 <i>Ø</i>	\$7 <i>00</i>	
FORSYTHIA X INTERMEDIA	BORDER FORSYTHIA	3' BB	\$5Ø	\$35Ø	
			ı		

landscape requirement

street tree	REQUIRED		PROVIDED
TOTAL NO. OF LOTS	<u> </u> 12		
ONE (I) DECIDUOUS PER LOT		12	12 (NOTE #
detention			
TOTAL LIN. FT. OF FREE BOARD LINE	375' <u>+</u>		
ONE (I) EVERGREEN TREE PER 100 LIN. FT.		3.75	6
ONE AND A HALF (1.5) DECIDUOUS TREE PER 100 LIN. FT.		5.60	6
FOUR (4) SHRUBS PER IOO LIN. FT.		15	21

I PROPOSED STREET TREE PLANTING PER CITY OF ROCHESTER HILLS SELECTION, LOCATION, AND INSTALLATION. STREET TREE PLANTING REQUIREMENTS TO BE PAID TOWARDS CITY STREET TREE FUND AT RATE OF \$200 PER TREE/LOT. TOTAL OF 12-TREES REQUIRED X \$200 = \$2,400





shrub planting detail

poor or severely disturbed soil or building rubble. use water to settle soil and remove air pockets and firmly set shrub. gently tamp if needed.

HATCHING DENOTES

5' WIDE PEDESTRIAN COLLECTOR WALK

PROPOSED STREET TREE

PER CITY SELECTION AND INSTALLATION. I-TREE PER

LOT. (TOTAL OF 12- TREES)

8688.53 Sq. Feet

0.20 Acres

AC&ACL-2

25' YEHICULAR CLEAR VIEW

3 x width of rootball

evergreen planting detail

DETENTION AREAS TO

POSITIVE DRAINAGE.

RÉCEIVE HYDROSEED ON

FINISH GRADES, PROVIDE

NEW AND DISTURBED AREAS

TO RECEIVE HYDROSEED ON

FINISH GRADES, PROVIDE

POSITIVE DRAINAGE.

<u>VMK-8</u>

Shortridge Avenue

do not prune terminal

leader or branch tips.

prune away dead or

broken branches only.

1A planting detail (detention pond)

EXISTING TREES TO REMAIN

stake with 2x2 hardwood stakes or approved equal driven 6"-8" outside of rootball.loosely stake tree trunk to allow for trunk flexing.stake trees just below first branch with 2"-3" wide belt-like, fabric straps (2 per tree on opposite sides of tree, connect from tree to stake horizontally. do not use rope wire thru a hose. remove all staking materials after set top of rootball level with grade

or slightly above grade if in clay soil. mulch 2"-3" depth with shredded hardwood bark. mulch shall be

neutral in color. leave 3" circle of

bare soil at base of tree trunk.

5' WIDE PEDESTRIAN COLLECTOR

PROPOSED POCKET PARK

SITE AMENITIES BY OTHERS

NEW AND DISTURBED AREAS

TO RECEIVE HYDROSEED ON .

planting detail (pocket park)

reference key location map

3 x width of rootball

SCALE 1"=120'-0"

do not prune terminal

leaderor branch tips.

prune away dead or

prune suckers off. -

set top of rootball level

with grade or slightly

above grade if in clay

center rootball in planting

unless planting in poor or

severely disturbed soil or

hole. leave bottom of planting

hole firm. do not amend soil

building rubble. use water to

settle soil and remove air

pockets and firmly set tree.

gently tamp if needed.

broken branches only.

FINISH GRADES, PROVIDE

POSITÍVE DRAINAGE.

fold down or pull back string, burlap or plastic exposing rootball. remove all non-degradable materials.

do not remove soil from the rootball.

break up (scarify) sides of planting hole.

center rootball in planting hole. leave bottom of planting hole firm do not amend soil unless planting in poor or severely disturbed soil or building rubble.use water to settle soil and remove air pockets and firmly set tree. gently tamp if needed.

tree planting detail



client:

VAQAR SIDDIQUI

3530 FOREST HILL ROAD BLOOMFIELD HILL, MI 48302 (313)-399-3915

project:

THE COMMONS **SOUTH**

project location: Rochester Hill Michigan Shortridge Ave. and Donaldson Road

sheet title:

LANDSCAPE **PLAN**

job no./issue/revision date: LS15.068.07 SPA 7-17-2015 LS15.068.10 SPA 10-10-2015 LS15.068.11 SPA 11-30-2015

drawn by:

do not stake trees unless in heavy

greater diameter tree trunk or large

crown. if staking is needed due to

these conditions:- stake with 2x2

hardwood stakes or approved equal

driven 6"-8" outside of rootball.- loosely

stake tree trunk to allow for trunk flexing.

- stake trees just below first branch with

2"-3" wide belt-like, fabric straps (2 per

tree on opposite sides of tree, connect

from tree to stake horizontally. do not

staking materials after 1 year.

remove nursery applied tree wrap,

tape or string from tree trunk and

crown. remove any tags or labels.

mulch 2"-3" depth with shredded

neutral in color. leave 3" circle of

hardwood bark. mulch shall be

bare soil at base of tree trunk.

fold down or pull back string,

burlap or plastic exposing rootball.

remove all non-degradable materials.

do not remove soil from the rootball.

break up (scarify) sides of

planting hole.

use rope wire thru a hose.).- remove all

clay soil, windy conditions, 3" or

checked by:

7-14-2015

notice:

Copyright This document and the subject matter contained therein is proprietary and is not to be used or reproduced without the written permission of Felino Pascual and Associates

Do Not scale drawings. Use figured dimensions only



The location and elevations of existing nderground utilities as shown on this is either expressed or implied as to the completeness of accuracy, contractor shall be exclusively responsible for determining the exact location and elevation prior to the start

project no:

LS15.068.07

of construction

sheet no: