# STORE 057 MINOR RESET CP-19-00057

3175 S. Rochester Road Rochester, MI 48307

## **Design Team**

ELEVATUS Architecture
111 E. Wayne Street, Suite 555
Fort Wayne, IN 46802
260 424-9080
Craig Armstrong, AIA

Engineering Resources, Inc. 11020 Diebold Rd. Fort Wayne, IN 46845 260 490-1025 Diane Reynolds

## Owner

Meijer, Inc. 2350 Three Mile Rd. Grand Rapids, MI 49544 616-735-8713 CHRIS MANKOWSKI

#### SHEET INDEX

G001	REV: 2/12		COVER SHEET & INDEX
C100	REV: 2/12	REV: 3/13	
C100E			SITE SURVEY
C101		REV: 3/13	
C200		REV: 3/13	
C201	REV: 2/12	REV: 3/13	SITE SIGNAGE, STRIPING AND SITE AMENITY PLAN
C201a	REV: 2/12	REV: 3/13	CONSTRUCTION FENCE STAGING PLAN
C300	REV: 2/12	REV: 3/13	SITE GRADING AND UTILITY PLAN
C301	REV: 2/12		SITE CONSTRUCTION EROSION CONTROL PLAN - NORTH
C302	REV: 2/12		SITE CONSTRUCTION EROSION CONTROL PLAN - SOUTH
C400	REV: 2/12		SITE DETAILS
C401	NEW		CITY OF ROCHESTER HILLS STORM SEWER DETAILS
C500	NEW	REV: 3/13	SITE DEMOLITION, LAYOUT AND GRADING PLANS FOR MILK BOSSE AREA
A100	REV: 3/13		OVERALL FLOOR PLAN
A101A			ARCHITECTURAL DEMOLITION & CONSTRUCTION PLAN - UNIT A
A101C			ARCHITECTURAL DEMOLITION & CONSTRUCTION PLAN - UNIT C
A101E	REV: 3/13		ARCHITECTURAL DEMOLITION & CONSTRUCTION PLAN - UNIT E
A201			EXTERIOR ELEVATIONS
ES101			ELECTRICAL SITE PLAN
ES102			ELECTRICAL SITE PLAN - PHOTOMETRICS



CONFIDENTIAL CONTROLL THE STATE OF THE STATE

CHARLEST ATT ATT OF THE AREA CONTROL TO THE AR

CHANGE NO OF CETALS IN STREET PROJECTION BY PARKETON




STORE 057 MINOR RESET CP-19-00057

B01808 1/21/2019
UBMITTAL
ssued for Bids, Permit, and Construction

Cover Sheet & Index

G001

OVERALL SITE PLAN




SITE LOCATION MAP SCALE: N.T.S.



CONSULTANT





FOR PERMITTING ONLY OWNER'S CONSTRUCTION VANAGER



# meijer

STORE #057 MINOR RESET

MEIJER PROJECT #: CP-19-00057

3175 S. Rochester Rd. Rochester Hills, MI 48307

2019 STORE REFRESH

REVISIONS				
Т	DESCRIPTION	DAT		
T	Revisions to Documents	02/12/2		
1	Revisions to Documents	03/13/2		
1				
L				

ISSUE DATE 12/21/2018 SUBJECT TAL

Overall Site Plan

C100

BUILDING SQUARE FOOTAGE: EXISTING: 281,436 SF PROPOSED: 276,135 SF

#### SURVEY NOTE:

EXISTING TOPOGRAPHY IS BASED ON A TOPOGRAPHICAL SURVEY PROVIDED BY REICHERT SURVEYING INC., DRAWING DATED NOVEMBER IN 2018. ADDITIONAL SITE INFORMATION WAS MERGED WITH THIS SURVEY. THE ADDITIONAL DESIGN DOCUMENTS WERE SUPPLIED TO ELEVATUS

SITE BENCHMARK PROVIDED FROM TOPOGRAPHIC SURVEY BY DEKEYSER

#### SITE PLAN NOTES:

1. OWNER INFORMATION MEIJER, INC. (GOOD WILL, INC.) 2350 THREE MILE ROAD GRAND RAPIDS, MI 49544

2. STORM DRAINAGE PATTERNS AND STORM WATER MANAGEMENT SHALL REMAIN AS EXISTING. NO INCREASE IN STORMWATER QUANTITY OR IMPERVIOUS AREA.

3. PROPOSED CONSTRUCTION IS NOT LOCATED IN A DESIGNATED FLOODPLAIN OR WETLAND AREA.

- THE LOND AREA.

  EXISTING UILITIES SHALL REMAIN EXCEPT AS INDICATED ON THE DRAWINGS.

  EXISTING BUILDING AND POLE-MOUNTED SITE LIGHTING FIXTURES SHALL REMAIN

  EXCEPT FOR ONE POLE LIGHT THAT IS BEING RELOCATED WITHIN THE GARDEN CENTER SEE ELECTRICAL DRAWINGS., ALL PROPOSED LIGHT FIXTURES IN PROPOSED CANOPIES (E.G. PHARMACY DRIVE-UP) AND IN GARDEN CENTER SHALL BE SHIELDED AS REQUIRED BY ZONING ORDINANCE LIGHTING REQUIREMENTS.
- EXISTING LANDSCAPING SHALL REMAIN.
- SEE ARCHITECTURAL DRAWINGS FOR CHANGES TO EXTERIOR SIGNAGE.

  SEE ARCHITECTURAL DRAWINGS FOR CHANGES TO EXTERIOR SIGNAGE.

#### FIRE DEPARTMENT NOTES:

ALL FIRE HYDRANTS SHALL REMAIN.

THE EXISTING BUILDING ADDRESS(S) SHALL REMAIN UNCHANGED. EXISTING FIRE LANES AND FIRE DEPARTMENT ACCESS ROAD WIDTHS SHALL REMAIN. FIRE LANES SHALL BE DESIGNATED BY THE FIRE CODE OFFICIAL, AND SHALL BE CONSPICUOUSLY POSTED ON BOTH SIDES OF THE FIRE LANE, WITH FIRE LAND SIGNS, SPACED NOT MORE THAN 100 FEET APART, FIRE LANE SIGNS SHALL READ 'NO STOPPING, STANDING, PARKING, FIRE LANE", AND SHALL CONFORM TO THE MICHIGAN MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES.

## EXISTING PARKING (MAIN STORE):

STORE PARKING LOT: 749 STANDARD SPACES 28 HANDICAP ACCES

EXISTING CART CORRALS: 17 CORRALS

PROPOSED PARKING (MAIN STORE):

28 HANDICAP ACCESSIBLE SPACES TOTAL SPACES

EXISTING CART CORRALS: 17 CORRALS

#### LOT INFORMATION:

MAIN STORE PARCEL #: 70-99-00-225-00\*

PROPERTY ZONING: B-3 FLEX BUSINESS OVERLAY

COUNTY: OAKLAND COUNTY TOWNSHIP: ROCHESTER HILLS

ACRES: 27.6± ACRES


#### LEGAL DESCRIPTION:

MEIJER STORE #57 - ROCHESTER HILLS, OAKLAND CO, MI (AFTER SALE TO JUST BURGERS & FRIES) OWNER: MEUER, INC.

A PART OF THE NORTHWEST 1/4 OF SECTION 35, T3N, R11E, CITY OF ROCHESTER HILLS, OAKLANG COUNTY, MICHIGAN, DESCRIBED AS:


REGINNING NR7\*47'36"E, 506 61 FEET FROM THE NORTHWEST CORNER OF SAID SECTION 35: THENCE N87'47'36'E, 742.59 FEET; THENCE SO2'12'26'E, 151.00 FEET; THENCE N87'47'36'E, 176.49 FEET; THENCE ALONG A TANGENT CURVE TO THE RIGHT 141.61 FEET, SAID CURVE HAVING A RADIUS OF 90.00 FEET, A CENTRAL ANGLE OF 90'09'06", AND A LONG CHORD BEARING \$47'07'51"E, 127.45 FEET THENCE S02"03'15"E, 537.56 FEET; THENCE S28'07'01"W, 179.50 FEET; THENCE S59'58'03"E, 65.00 FEET; THENCE S30°0205"W, 180.94 FEET; THENCE S87°48'01"W, 785.96 FEET; THENCE W22°04'09"W, 38.36 FEET; THENCE S87°47'32"W, 145.23 FEET; THENCE N02°12'08"W, 49.54 FEET; THENCE NS0°46'35"W, 206.76 FEET; THENCE S87'45'48"W, 211.98 FEET TO A POINT ON THE EAST RIGHT OF NSO 4635"W, 206.76 FEET; THENCE S87 4548"W, 211.38 FEET TO A POINT ON THE EAST RIGHT OF WAY LINE OF ROCHESTER ROAD (M-150 VARRIBLE WIDTH); THENCE NO2'0059"W, 30.56 FEET ALONG SAID RIGHT OF WAY LINE OF ROCHESTER ROAD; THENCE 572'55'39"E, 16.88 FEET; THENCE NSO 590"E, 154.80 FEET; THENCE ALONG A NON-TANGENT CURVE TO THE LEFT, 22.47 FEET, SAID CURVE HAVING A RADIUS OF 24.00 FEET, CHARTRIAL ANGLE OF 53'39"G\*, AND A CHORD BEARING NS9'2236"E, 21.66 FEET; THENCE N22'330"C\*, 41.66 FEET; 41.66 FEET THENCE N87'59'01"E, 43.14 FEET; THENCE ALONG A TANGENT CURVE TO THE LEFT 22.81 FEET, SAID CURVE HAVING A RADIUS OF 14.50 FEET, A CENTRAL ANGLE OF 90°07'36", AND A LONG CHORD CURVE TRAINED A ROBOLO OF 14-30 FEET, THENCE NOZOSSI'W, 214.0 90 7-30 , ARIO A CURVE CHOING A TANGENT CURVE TO THE LEFT 11.50 FEET, SAID CURVE HAVING A RADIUS OF 8.50 FEET, A CENTRAL ANGLE OF 77-31'SS', AND A LONG CHORD BEARING NAO'S4'SS''W, 10.64 FEET TO A POINT OF REVERSE CURVATURE; THENCE ALONG SAID REVERSE CURVE TO THE RIGHT 18.27 FEET, SAID CURVE HAVING A RADIUS OF 59.30 FEET, A CENTRAL ANGLE OF 17\*39'10", AND A LONG CHORD BEARING N70\*50'59"W 18-20 FEET, THENCE NG2\*0125\*W, 74.28 FEET, THENCE S89\*3652\*W, 110.84 FEET, THENCE S89\*3652\*W, 110.84 FEET, THENCE S89\*3652\*W, 10.84 FEET, THENCE S89\*3652\*W, 62.55 FEET TO A POINT ON THE EAST RIGHT OF WAY UNE OF SAID ROCHESTER ROAD; THENCE NO2\*0059\*W, 101.61 FEET ALONG SAID RIGHT OF WAY UNE OF ROCHESTER ROAD; THENCE ROAD ON-TANGENT CURVE TO THE LEFT, 48.95 FEET, SAID CURVE HAVING A RADIUS OF 65.74 FEET, A CENTRAL ANGLE OF 42"39'28", AND A CHORD BEARING TAVINO A RADIUS OF 63.74 FEET, A CENTINAL ARIGE OF 42.59.28, ARID A CHURD BEARING SESTI11/28°E, 47.84 FEET; THENCE SES 23'11'12" 4.746 FEET; THENCE ALONG A TANGENT CURVE TO THE LEFT, 26.64 FEET, SAID CURVE HAVING A RADIUS OF 21.93 FEET, A CENTRAL ANGLE OF 69'35'21", AND A CHORD BEARING N62'41'08"E, 25.03 FEET; THENCE N27'53'28"E, 44.28 FEET; THENCE N42'50'28"E, 13.79 FEET; THENCE ALONG A TANGENT CURVE TO THE RIGHT, 40.29 FEET, SAID CURVE HAVING A RADIUS OF 79.74 FEET, A CENTRAL ANGLE OF 28°56'59", AND A CHORD REARING N57°18'58"E, 39.86 FEET, THENCE NO2'00'59"W, 30-EET, THENCE N87"4"31"E, 118.16 FEET, THENCE 802'36'28"E, 23-30.0


21.14 FEET, THENCE ALONG A CURVE TO THE LEFT 271.63 FEET, SAID CURVE HAVING A RADIUS OF 186.00 FEET, A CENTRAL ANGLE OF 83" 40' 27" AND A LONG CHORD BEARING OF N39"37'49"E, 248.13 FEET; THENCE NO2'12'24'W, 126.00 FEET; THENCE ALONG A CURVE TO THE LEFT 62.83 FEET, SAID CURVE HAVING A RADIUS OF 40.00 FEET, A CENTRAL ANGLE OF 90' 00' 00" AND A LONG CHORD BEARING OF N47'12'24'W, 56.57 FEET; THENCE N02'12'24'W, 33.00 FEET TO THE POINT OF BEGINNING AND CONTAINING 27.56 ACRES OF LAND.




CAR STACKING ENLARGEMENT


CITY FILE #19-003 SECTION #35







SECTION #3









#### ALL ITEMS AND RELATED WORK NOTED BELOW TO BE SUPPLIED BY THE CONTRACTOR AT HIS MER EXPENSE PER THE CONTRACT DOCUMENTS. 1 DECORATIVE BOLLARD PER DETAIL AS/C400. (2) GUARD POST PER DETAIL AS/C400. A PAINT DETECTABLE WARNING AREA PER DETAIL A4/C400. (4) 6'-0" HIGH GARDEN CENTER ORNAMENTAL FENCE, (SEE ARCH, PLANS). (5) 6'-0" HIGH GARDEN CENTER ORNAMENTAL GATE, (SEE ARCH, PLANS). 6) 3'-0" TALL X 6'-0" SOLID PAINTED LETTERS, WHITE, SEE PLAN FOR WORDING.

TO STOP BAR MARKING SHALL BE SINGLE SOLID 24" WHITE WATERBORNE PAIN 8 4' SINGLE SOLID LINE, YELLOW.

9 "STOP SIGN" (ONE SIDE) PER DETAIL C2/C400.

CONSTRUCTION NOTES:

(10) CROSSWALK PER DETAIL C1/C400,
(11) "HANDICAP SIGNS" (BOTH SIDES) PER DETAIL C2/C400.

REMOVE TEMPORARY BLACK TAPE AND RE-STRIPE HANDICAP PAVEMENT MARKINGS, COLOR TO MATCH EXISTING.

(13) LANE ARROW PER DETAIL D2/C400.

14) "PHARMACY DRIVE-THRU" (ONE SIDE) SIGN PER DETAIL C2/C400.

15 "DO NOT ENTER" SIGN (ONE SIDE) PER DETAIL C2/C400.

16) NEW LIGHT POLE (SEE SITE ELECTRICAL PLANS)

7 REMOVE TEMPORARY BLACK TAPE AND RE-STRIPE EXISTING LINE WITH A 4\* SINGLE, SOLID LINE, YELLOW (18) GARDEN CENTER ORNAMENTAL FENCE INSTALLED ON TOP OF EXISTING BRICK WALL, TOP OF FENCE SHALL BE AT 19-0" ABOVE FINISHED GRADE, HEIGHT OF BRICK WALL VARIES. (SEE ARCH. PLANS).

(9) 3'-6" TALL PEDESTRIAN CONSTRUCTION FENCE. REMOVE AFTER CONSTRUCTION IS COMPLETE.

6-0" TALL PEDESTRIAN CONSTRUCTION FENCE. REMOVE AFTER CONSTRUCTION IS COMPLETE.

(21) "FIRE LANE NO PARKING" SIGN (BOTH SIDES) PER DETAIL C2/C400.

(22) TEMPORARY DRIVE PAVEMENT MARKINGS TO BE 4' SINGLE SOLID LINE, COLOR TO BE WHITE AND MATERIAL TO BE TAPE. REMOVE AFTER PROJECT IS COMPLETE.

4° SINGLE SOLID, YELLOW, LINE ALONG EDGE OF DRIVEWAY AND TOP OF CURB.

"NOT ALL KEYNOTES USED ON THIS PAGE.





Know what's below. Call before you dig. **ELEVATUS** 111 E. Wayne Street, Suite 555. Fort Wayne, IN 45802 263 424-9080 Elevatus Architecture.com

COMPIDENTIAL COPYRIGHT 2017 SZ ARCHTECTS, LLC «Cu ELEVATUS ARCHTECTURE

CONSULTANT



Davil J. Schol FOR PERMITTING ONLY

WHER'S CONSTRUCTION VANAGER





STORE #057 MINOR RESET

MEIJER PROJECT #: CP-19-00057

3175 S. Rochester Rd.

2019 STORE REFRESH


NO.	DESCRIPTION	DATE
1	Revisions to Documents	02/12/2019
2	Revisions to Documents	03/13/2019
-		

PROJECT NO. 1801808 ISSUE DATE 12/21/2018 SUBMITTAL Permit Set


Construction Fence Staging Plan

C201a

CITY FILE #19-003 SECTION #35



SECTION #35



ELEVATUS ARCHITECTURE

111 E. Wayne Street, Surte 555, Fort Wayne, IN 4 263 424-9080 Elimatus Architecture

CONFIDENTIAL COPYRIGHT 2017
\$148CHTFCTS 11C dia BLEVATUS ARCHITECTURE

ASSAN TO HECTOR UP THE CONTROL AT 11 ALL DUESTS, HAN EXCENSIVE AND PLANT EXCHANGED AN ACCOUNTED RESISTED IN PRODUCTION OF THE CONTROL OF THE PLANT AND PRODUCTION OF THE CONTROL OF THE PLANT AND ACCOUNTED AND ACCOUNTED THE PLANT AND ACCOUNTED AND MARKED ACCOUNTED THE ACCOUNTED THE PLANT AND ACCOUNTED AND ACCOUNTED AND ACCOUNTED THE PLANT AND ACCOUNTED AND ACCOUNTED AND ACCOUNTED TO ACCOUNTED AND ACCOUNTED AND ACCOUNTED AND ACCOUNTED TO ACCOUNTED AND ACCOUNTED AND ACCOUNTED ACCOUNTED TO ACCOUNTED AND ACCOUNTED AND ACCOUNTED ACCOUNTED ACCOUNTED AND ACCOUNTED AND ACCOUNTED AND ACCOUNTED ACCOUNTED ACCOUNTED ACCOUNTED AND ACCOUNTED AND ACCOUNTED ACCOUNTED ACCOUNTED ACCOUNTED AND ACCOUNTED AC

The LEAT ON BY THAT HAS A CAT OF A SEALTH OF THE ANALYSIS AND A CAT OF A CA

HETTER DICH STORE ON THE TOOL WINDS SHALL HAVE PRECEDED ON CHARLESON, CONTINUENDES SHALL HERF HAS SER SHIPMENE HEN HALL ON HAS CONTINUED ON THE LOS HAD THE STORES HAVE SHIPMEN OF HAT HAS FOUNT HE BROWNED HAD CONTINUED SHOWS IN THE STORESON, WHO PROMISED HAS DO SOUTH HAS THE SERVETTER TO THE OFFICE FOR HEAD AND CONTINUED HAS CONTINUED TO THE OFFICE FOR HEAD AND CONTINUED HAS CONTINUED TO THE OFFICE FOR HEAD AND CONTINUED HAS CONTINUED TO THE OFFICE FOR HEAD AND CONTINUED HAS CONTINUED TO THE OFFICE FOR HEAD AND CONTINUED HAS CONTINUED TO THE OFFICE FOR HEAD AND CONTINUED TO THE OFFICE FOR HEAD AND CONTINUED TO THE OFFICE FOR THE OFFICE FOR HEAD AND CONTINUED TO THE OFFICE FOR THE OFFICE FOR

CONSULTANT



11020 Diebold Road, Fort Wayne, IN 45845 Pt: (260) 490-1025 Fax: (260) 490-1026

12-21-2018

12-21-2018

OF #1 OF #1

ROCKFORD CONSTRUCTION



STORE #057 MINOR RESET

MEIJER PROJECT #: CP-19-00057

3175 S. Rochester Rd. Rochester Hills, MI 48307

2019 STORE REFRESH

PROJECT NO. ISSUE DATE
1801808 12/21/2018
SUBJETTAL

Site Construction Erosion

Control Plan - North


C301

CITY FILE #19-003 SECTION #35

03



## SITE CONSTRUCTION EROSION CONTROL PLAN - SOUTH



SITE LOCATION MAP SCALE: NONE

#### FUELING AREA AND VEHICLE AND **EQUIPMENT MAINTENANCE /** MATERIAL STORAGE NOTE:

- ON-SITE VEHICLE AND EQUIPMENT FUELING SHALL ONLY BE USED WHERE IT IS IMPRACTICAL TO SEND VEHICLES AND EQUIPMENT OFF-SITE FOR FUELING.
- IF ON-SITE FUELING IS NECESSARY, CONTRACTOR SHALL DESIGNATE A DEDICATED AN AREA TO BE USED.
- CONTRACTOR SHALL SUPPLY, CLEARLY MARK, AND KEEP CLEAN-UP MATERIALS AND SPILL KITS AVAILABLE IN FUELING
- CONTRACTOR SHALL USE DRIP PANS OR ABSORBENT PADS DURING VEHICLE AND EQUIPMENT FUELING UNLESS FUELING IS CONDUCTED IN A DESIGNATED AREA, OVER AN IMPERMEABLE CONTAINMENT AREA.
- FUELING AREAS SHALL BE ON LEVEL GRADE AND PROTECTED FROM STORM WATER RUN-ON AND RUN-OFF AND BE AT LEAST 100 FT FROM DOWNSTREAM DRAINAGE FACILITIES AND
- CONTRACTOR SHALL USE FUELING NOZZLES WITH AUTOMATIC SHUT-OFFS, FUELING OPERATIONS SHALL NOT BE LEFT UNATTENDED.
- CONTRACTOR SHALL PROTECT FUELING AREAS WITH IMPERMEABLE BERMS AND OR DIKES TO PREVENT STORM WATER RUN-ON, RUN-OFF AND TO CONTAIN SPILLS.
- CONTRACTOR SHALL NOT "TOP-OFF" FUEL TANKS
- CONTRACTOR SHALL INSPECT VEHICLES AND EQUIPMENT EACH DAY FOR LEAKS, IF LEAKS ARE FOUND, THEY MUST BE REPAIRED AND CLEANED-UP IMMEDIATELY AND/OR THE LEAKING VEHICLES OR EQUIPMENT REMOVED FROM THE
- CONTRACTOR SHALL DISPOSE OF ANY USED ABSORBENT SPILL KIT MATERIALS AND ANY CONTAMINATED SOILS ACCORDING TO FEDERAL, STATE AND LOCAL REGULATIONS.

#### VEHICLE AND EQUIPMENT MAINTENANCE / MATERIAL STORAGE AREA

- CONTRACTOR SHALL DESIGNATE A DEDICATED AREA TO BE USED IF STORING MATERIALS, MAINTAINING OR STORING VEHICLES AND EQUIPMENT ON-SITE.
- STORAGE / MAINTENANCE AREAS SHALL BE ON LEVEL GRADE AND PROTECTED FROM STORM WATER RUN-ON AND RUN-OFF AND BE AT LEAST 100 FT FROM DOWNSTREAM DRAINAGE FACILITIES AND WATERCOURSES,
- CONTRACTOR SHALL USE DRIP PANS OR ABSORBENT PADS DURING VEHICLE AND EQUIPMENT MAINTENANCE UNLESS MAINTENANCE IS CONDUCTED IN A DESIGNATED AREA, OVER AN IMPERNEABLE CONTAINMENT AREA.
- CONTRACTOR SHALL SUPPLY, CLEARLY MARK, AND KEEP CLEAN-UP MATERIALS AND SPILL KITS AVAILABLE IN STORAGE / MAINTENANCE AREAS.
- CONTRACTOR SHALL PROTECT STORAGE / MAINTENANCE AREAS WITH IMPERMEABLE BERMS AND OR DIKES TO PREVENT STORM WATER RUN-ON, RUN-OFF AND TO CONTAIN SPILLS.
- TRACTOR SHALL PROVIDE IMPERMEABLE SPILL TAINMENT DIKES OR SECONDARY CONTAINMENT AROUN RED OIL AND CHEMICAL DRUMS.
- CONTRACTOR SHALL DISPOSE OF ANY USED ABSORBENT SPILL KIT MATERIALS AND ANY CONTAMINATED SOILS ACCORDING TO FEDERAL, STATE AND LOCAL REGULATIONS.



#### STABLE CONSTRUCTION ENTRANCE AND CONCRETE WASHOUT NOTE:

CONTRACTOR SHALL PROVIDE A STABLE CONSTRUCTION ENTRANCE THAT IS CONVENIENT TO THE PROJECT SITE. THIS CONSTRUCTION ENTRANCE SHALL EITHER BE COMPRISED OF 1'-3' AGGREGATE, 60' x 12' x 6" THICK OR A MANUFACTURED TRACK-OFF DEVICE. THE STRUCTION ENTRANCE SHALL PROVIDE PROTECTION AGAINST MUD AND SEDIMENT BEING TRACKED OFF THE CONSTRUCTION SITE INTO ADJACENT PUBLIC OR PRIVATE PAVEMENT, IF MUD OR ONTO ADJACENT PUBLIC OR PRIVATE PAYEMENT. IF MUD OR SEDIMENT IS TRACKED ON TO ADJACENT PAYED SURFACES. THE CONTRACTOR SHALL CLEAN THE SURFACES DAILY BY SCRAPING AND BRUSHING THE SEDIMENT OFF THE SURFACE AND RETURNING IT TO THE SOURCE LOCATION. THE SURFACE SHALL NOT BE CLEANED BY USE OF FLUSHING WITH WATER.

CONTRACTOR SHALL PROVIDE A CONCRETE WASHOUT AREA TO BE USED DURING THE CONSTRUCTION OF THE UTILITIES, SIDEWALKS AND BUILDING, THE CONCRETE WASHOUT STRUCTURE MAY BE CONSTRUCTED ON-SITE OR A MANUFACTURED DEVICE, PLACE THE CONCRETE WASHOUT STRUCTURE AN MINIMUM OF 50 FROM AN STORM WATER INLET OR CATCH BASIN AND EXCESS CONCRETE REMOVED AT 50% OF THE DESIGN CAPACITY.

#### CITY OF ROCHESTER HILLS **EROSION CONTROL NOTES:**

- ALL EROSION AND SEDIMENT CONTROL WORK SHALL CONFORM TO STANDARDS AND SPECIFICATIONS OF THE OAKLAND COUTNY DRAIN COMMISSIONER.
- ALL TEMPORARY AND PERMANENT SOIL EROSION AND SEDIMENT CONTROL MEASURES SHALL CONFORM TO THE CITY OF ROCHESTER HILLS CURRENT MS4 PERMIT, ANY CONFLICT BETWEEN THESE STANDARDS AND THE MS4 PERMIT, THE PERMIT'S CONDITIONS SHALL TAKE PRECEDENCE.
- DAILY INSPECTIONS SHALL BE MADE BY THE CONTRACTOR FOR EFFECTIVENESS OF EROSION AND SEDIMENTATION CONTROL MEASURES, AND ANY NECESSARY REPAIRS SHALL BE PERFORMED WITHOUT DELAY.
- ANY SEDIMENTATION FROM WORK ON THIS SITE SHALL BE CONTAINED ON THE SITE AND NOT ALLOWED TO COLLECT ON ANY OFF-SITE AREAS OR IN WATERWAYS.
- CONTRACTOR SHALL APPLY TEMPORARY EROSION AND SEDIMENTATION CONTROL MEASURES WHEN REQUIRED AND AS DIRECTED ON THESE PLANS, TEMPORARY MEASURES SHALL BE REMOVED AS SOON AS PERMANEN STABILIZATION OF EARTH CHANGES HAVE BEEN ACCOMPLISHED PER OAKLAND COUNTY DRAIN COMMISSIONER'S STANDARDS.
- STAGING THE WORK WILL BE DONE BY THE CONTRACTOR
  AS DIRECTED IN THESE PLANS AND AS REQUIRED TO ENSURE PROGRESSIVE STABILIZATION OF DISTURBED
- SOIL EROSION CONTROL PRACTICES SHALL BE ESTABLISHED IN THE EARLY STAGES OF CONSTRUCTION BY THE CONTRACTOR, SEDIMENT CONTROL PRACTICES WILL BE APPLIED AS A PERIMETER DEFENSE AGAINST AN TRANSPORTING OF SILT OFF THE SITE.
- FAILURE TO COMPLY WITH APPROVED SOIL EROSION ANI SEDIMENTATION MEASURE MAY RESULT IN WORK STOPPAGE BY APPROPRIATE AUTHORITY,
  EXCEPTIONS TO TIMING OF CONTROL MEASURES'
- INSTALLATION WILL ONLY BE PERMITTED WHERE TREES AND STUMPS NEED TO BE REMOVED TO INSTALL SOIL CONTRACTOR IS TO PROVIDE THE CITY WITH PERMIT RENEWALS, VIOLATION CORRECTIONS, AND/OR RELEASES


#### PERMANENT OFF-SITE EXCESS SOIL AREA AND WETLAND NOTE:

EXCESS SOIL IS TO BE REMOVED FROM PROJECT SITE TO A PERMANENT SITE, IT IS THE CONTRACTOR'S RESPONSIBILITY TO FI A SITE TO PERMANENTLY PLACE THE EXCESS SOIL, EXECUTE ANY CONTRACTS NEEDED WITH THE PROPERTY OWNER, AND RESEARC FOR THE POSSIBILITY OF WETLANDS ON THE EXCESS SOIL SITE. IF WETLANDS ARE FOUND, ANOTHER SITE SHOULD BE CHOSEN, IF THE CONTRACTOR WISHES TO USE A SITE THAT CONTAINS WETLANDS I IS THE CONTRACTORS FINANCIAL RESPONSIBILITY TO HAVE THE ETLANDS ASSESSED AND DELINEATED BY A CERTIFIED WETLANDS ASSESSED AND DELINEATED BY A CERTIFIED ENVIRONMENTAL CONSULTING FIRM. IT IS THE CONTRACTORS RESPONSIBILITY TO PROVIDE EROSION CONTROL DRAWINGS OF THE EXCESS SOIL SITE TO THE ROCHESTER HILLS MS4 COORDINATOR FOR INSPECTION AND APPROVAL, TO ASSURE APPROPRIATE MEASURES WILL BE TAKEN TO PROTECT THE WETLANDS AND THAT THE WETLANDS WILL NOT BE DISTURBED. THE EXCESS SOIL PROPERTY SHALL HAVE EROSION CONTROL MEASURES AND DEVICES IN PLACE IN ACCORDANCE WITH THE LATEST INDIANA STORM WATER QUALITY MAIUAL AND ANY LOCAL ORDINANCE. CONTRACTOR SHALL HAVEN THE PROSPOUL CONTROL MEASURES. AND DEVICES IN SECTION. MAINTAIN THE EROSION CONTROL MEASURES AND DEVICES USED. IN ACCORDANCE WITH THE LATEST INDIANA STORM WATER QUALITY ACCOMMANCE WITH THE CATEST INDIVINA STORM WATER QUALITY MANUAL AND LOCAL ORDINANCES, THE SITE SHALL BE FINE GRADED, SOIL STABILIZED, AND TEMPORARY EROSION CONTROL DEVICES AND MEASURES REMOVED AT THE COMPLETION OF SOIL PLACEMENT.

#### **EROSION CONTROL LEGEND:**

INLET PROTECTION / FILTER CONSTRUCTION LIMITS

#### **EROSION CONTROL KEY:**



#### OAKLAND COUNTY EROSION CONTROL INSPECTION AND MAINTENANCE NOTE:

AS PER THE OAKLAND COUNTY WATER RESOURCE COORDINATOR SOIL EROSION AND SEDILENT CONTROL MANUAL. THE CONTRACTOR IS RESPONSIBLE FOR MAINTENANCE OF THE REPOSION CONTROL DEVICES AND MEASURES. THE EROSION CONTROL DEVICES AD MEASURES SHALL BE BE INSPECTED AND MAINTAINED. AMINIMUM OF ONCE PER NEEK AND AFTER EVERY STORM EVENT.

#### **EROSION CONTROL NOTES:**

#### PRE-CONSTRUCTION ACTIVITY

- CONTACT THE MICHIGAN UTILITIES PROTECTION SERVICE \*MICHIGAN 811\* TO LOCATE UNDERGROUND UTILITIES AT LEAST TWO (2) WORKING DAYS PRIOR TO EARTH DISTURBING ACTIVITIES, MARK UTILITIES ON THE PROJEC
- PRESERVE AND PROTECT TREES, SHRUBS, EXISTING VEGETATION AND EXISTING ITEMS TO REMAIN ON THE
- ESTABLISH EQUIPMENT AND EMPLOYEE PARKING AND
  - STAGING AREAS.
    PROTECT EXISTING STORM WATER SEWER SYSTEM INLETS WITH INLET PROTECTION DEVICES. ANY STORM SEWER STRUCTURES LOCATED CLOSE TO PROPOSED WORK
    SHALL HAVE INLET PROTECTION DEVICES INSTALLED. INLET PROTECTION SHALL BE FLEXSTORM WITH OVERFLOW HOLE AS MANUFACTURED BY PIPE AND INLET PROTECTION, INC. OR APPROVED EQUAL. INSTALL PER MANUFACTURER'S RECOMMENDATIONS.


- BEGIN DEMOLITION OF ITEMS TO BE REMOVED FOR THE
- PROPOSED CONSTRUCTION.
  INSTALL CONCRETE WASHOUT AREA(S) TO BE USED DURING CONSTRUCTION OF ROADS, PARKING LOTS. SIDEWALKS AND BUILDINGS CONTRACTOR TO USE PREFABRICATED PORTABLE CONCRETE WAS SYSTEMS / CONTAINERS WITH A MINIMUM SUMP CAPACIT OF 2 CU YDS.
- PLACE INLET PROTECTION DEVICES AT ALL INLETS SPECIFIED ON THE SITE GRADING AND UTILITY PLAN. CONSTRUCT UTILITIES, PARKING LOTS, SIDEWALKS AND
- BUILDING ADDITIONS.
  REMOVE TEMPORARY EROSION CONTROL DEVICES AND MEASURES ONCE THE CONTRIBUTING DRAINAGE AREA IS STABILIZED, AND STABILIZE ANY DISTURBED SOIL WITH

#### **EROSION CONTROL DEVICE** MONITORING AND MAINTENANCE

- INSPECT WEEKLY AND AFTER ½" STORM EVENTS FOR SEDIMENT AND DEBRIS. REMOVE SEDIMENT (NOT BY FLUSHING) WHEN THE CONTAINMENT AREA BECOMES MORE THAN HALF FULL OF SEDIMENT.
- REMOVE ANY CAKED-ON SILT FROM THE SEDIMENT BAG AND REVERSE FLUSH THE BAG.
- INSPECT BAG CLAMPING BAND AND SUSPENSION HANGERS, REPLACE BAG IF THE GEOTEXTILE IS TORN OR PUNCTURED TO X\* DIAMETER OR GREATER ON THE LOWER HALF OF THE BAG, REPLACE CLAMPING BAND AND SUSPENSION HANGERS IF DAMAGED OR CORROCED.
- REMOVE ALL ACCUMULATED SEDIMENT AND DEBRIS FROM VICINITY OF THE UNIT AFTER EACH STORM EVENT.
  - DEPOSIT THE SEDIMENT WHERE IT WILL NOT ENTER THE

## CURB AND GUTTER INLET FILTER

(BEFORE AND AFTER PAVING)
MATERIAL: CATCH-ALL, ULTRA-URBAN FILTERS,



INLET FILTER INSERT GEOTEXTILE FILTER FABRIC (MIN 100 GAL/MIN/SQ FT) SECTION A-A

ALTERNATIVE "A" (SI-4A)

CP-19-00057 3175 S. Rochester Rd. Rochester Hills, MI 48307

RESET

2019 STORE REFRESH

**ELEVATUS** 

11 E. Wayne Street, Suite 555, Fort Wayne, BN 48802 260 424-9080 Elevatus Architecture, con

PARSON TO SECTION AS OF FOUR PROPERTY AS A SECURITY ESSAURATION OF THE PARSON TO SECURITY ESSAURANCE AND AN ADMINISTRATION OF THE PARSON AND ADMINISTRATION OF THE PARSON AND ADMINISTRATION AND ADMINISTRATION OF THE PARSON ADMINISTRATION

INGNEERING

Danil J. Schol

FOR PERMITTING ONLY

**ROCKFORD** 

meijer

STORE #057 MINOR

MEIJER PROJECT #:

ANERS CONSTRUCTION VANAGER

12-21-2018

CONFIDENTIAL COPYRIGHT 2017
SY ARCHITECTS 11.C dea BLEVATUS ARCHITECTURE

CONSULTANT

DESCRIPTION Revisions to Documents


PROJECT NO. ISSUE DATE


Site Construction Erosion Control Plan - South


C302



### LOW POINT INLET FILTER ALT. "A" (SI-2A) MATERIAL: CATCH-ALL, ULTRA-URBAN FILTERS FLOGARD +PLUS OR APPROVED ALTERNATIVE







CITY FILE #19-003