APRIL, 2021

CITY FILE # 21-022 SECTION # 35



NOTES

- ① CONCRETE CURB & GUTTER SEE DETAIL SHEET C105
- 2 CONCRETE SIDEWALK SEE DETAIL SHEET C105
- 3 4" WIDE PAINTED LINE PER MUTCD (YELLOW)
- 4 CONCRETE BUILDING CURB SEE DETAIL SHEET C105
- 5 BOLLARD SEE DETAIL SHEET C105
- 6 PAINTED DIRECTIONAL ARROWS PER MUTCD
- 7 DRIVE-THRU MENU BOARD
- 8 BYPASS LANE
- 9 ASPHALT PAVING SEE DETAIL SHEET C105
- (10) SEALCOAT PAVEMENT TO OBSCURE EXISTING PARKING STRIPING
- 11 TRASH ENCLOSURE w/ CONC. PAVING- SEE DETAIL SHEET C105
- 12 INSTALL ADA SIGNAGE AND STRIPING
- 13 LEASE AREA
- 14 HANDRAIL
- (5) AREA TO RECEIVE GRASS, STONE MULCH OR ARTIFICAL TURF
- 16 ADA CURB RAMP
- TO STEPS WITH HANDRAIL 4 RISERS
- 18 PEDESTRIAN CROSSWALK

Site Plan Review

Reviewed for compliance to the City Ordinance, Building and Fire Codes

| Department | Reviewer | Approved | | |
|---|---|----------|--|--|
| Planning | Kristen Kapelanski 248-841-2772 KapelanskiK@RochesterHills.org | Yes | | |
| Building | Mark Artinian 248-841-2446 ArtinianM@RochesterHills.org | Yes | | |
| ngineering | Jason Boughton 248-841-2490 BoughtonJ@RochesterHills.org | Yes | | |
| Traffic | Keith Depp 248-841-2503 DeppK@RochesterHills.org | Yes | | |
| Nat. Resources | Matt Einheuser 248-841-2551 EinheuserM@RochesterHills.org | Yes | | |
| ire | Lt. Ann Echols 248-841-2701 EcholsA@RochesterHills.org | Yes | | |
| City of Rochester Hills Planning & Economic Development | | | | |

Conditions and mark-ups noted throughout the plan set must be addressed prior to final approval.

666 McKinley Ave. Alpena, MI 49707

(877) 422-8233

S B IGGI

-REMOVE ALL WIRE AND BURLAP

-7.62 CM (3") SHREDDED BARK MULCH CAGRIFORM PLANT FOOD TABLETS

COMPACTED BACKFILL SAUCER -OMIT SAUCER WHEN IN PLANT

BACKFILL MIXTURE TO BE 1/3 SAND,

COMPACTED BACKFILL MIXTURE

1/3 TOPSOIL, AND 1/3 PEAT

-25.4 CM (10") DEEP MIN.

FROM TOP OF ROOTBALL

L101 Landscape Plan 120121 andrew.filler

APRIL, 2021



1 regulated tree is shown to be removed and will either need to be replaced or payment made into the the City Tree fund. Current Plant Material list does not include any tree species that would meet replacement requirements. Please add tree species to landscape plan or note that payment will be made into the City tree fund (\$304).

1. ALL LANDSCAPE AREAS SHALL BE HAVE DRAUGHT RESISTENT PLANTINGS

- 2. LANDSCAPING SHALL BE KEPT IN A NEAT, ORDERLY AND HEALTHY GROWING CONDITION, FREE FROM DEBRIS AND REFUSE.
- 3. PRUNING SHALL BE MINIMAL AT THE TIME OF INSTALLATION, ONLY TO REMOVE DEAD OR DISEASED BRANCHES. SUBSEQUENT PRUNING SHALL ASSURE PROPER MATURATION OF PLANTS TO ACHIEVE THEIR APPROVED PURPOSE.
- 4. ALL DEAD, DAMAGED, OR DISEASED PLANT MATERIAL SHALL BE REMOVED IMMEDIATELY AND REPLACED WITHIN SIX MONTHS AFTER IT DIES OR IN THE NEXT PLANTING SEASON, WHICHEVER OCCURS FIRST. FOR PURPOSES OF THIS SECTION, THE PLANTING SEASON FOR DECIDUOUS PLANTS SHALL BE BETWEEN MARCH 1 AND JUNE 1 AND FROM OCTOBER 1 UNTIL THE PREPARED SOIL BECOMES FROZEN. THE PLANTING SEASON FOR EVERGREEN PLANTS SHALL BE BETWEEN MARCH 1 AND JUNE 1. PLANT MATERIAL INSTALLED TO REPLACE DEAD OR DISEASED MATERIAL SHALL BE AS CLOSE AS PRACTICAL TO THE SIZE OF THE MATERIAL IT IS INTENDED TO REPLACE. THE CITY MAY NOTIFY PROPERTY OWNERS OF THE NEED TO REPLACE DEAD, DAMAGED, OR DISEASED MATERIAL.
- 5. THE APPROVED LANDSCAPE PLAN SHALL BE CONSIDERED A PERMANENT RECORD AND INTERGRAL PART OF THE SITE PLAN APPROVAL. UNLESS OTHERWISE APPROVED IN ACCORDANCE WITH THE AFOREMENTIONED PROCEEDURES, ANY REVISIONS TO OR REMOVAL OF PLANT MATERIALS, OR NON-COMPLIANCE WITH THE MAINTENANCE REQUIREMENTS OF ZONING ORDINANCE SECTIN 138-12.109 WILL PLACE THE PARCEL IN NON-CONFORMITY WITH THE APPROVED LANDSCAPE PLAN AND BE AIVIOLATION OF THE ORDINANCE.
- 6. IF PROTECTED TREES ARE DAMAGED, A FINE SHALL BE ISSUED ON AN INCH-BY-INCH BASIS AT A MONITARY RATE AS DEFINED BY THE FORESTRY DEPARTMENT.

LANDSCAPE MAINTENANCE NOTES

- 1. ALL TREES SHALL RECEIVE A 5' DIAMETER RING OF EVENLY SPREAD HARDWOOD BARK MULCH 3" THICK.
 - 2. CONTRACTOR SHALL NOTIFY OUPS AT 811 TO LOCATE ANY UNDERGROUND UTILITY LINES OR STRUCTURES PRIOR TO STARTING CONSTRUCTION.

MIN. REQ'D SIZE

3 CONT.

2 CONT.

3 CONT.

- THREE (3) REINFORCED RUBBER HOSE SECTIONS WITH DOUBLE STRAND OF

- WRAP #11 DOUBLE STRAND WIRE AT LEAST TWICE AROUND

WRAP TREE FROM BOTTOM UP WITH 50% OVERLAP AND

- POST SPACED EVENLY AT 18" -WOOD OR STEEL AS DIRECTED BY OWNER'S REPRESENTATIVE

#11 WIRE

EACH POST

ROOTBALL

SAUCER

1/3 PEAT

TIE SECURELY

BURLAP FROM TOP OF

FINISHED GRADE

- 3" SHREDDED BARK MULCH

6"x12" COMPACTED BACKFILL

- AGRIFORM PLANT FOOD TABLETS

- 10" DEEP MIN. COMPACTED BACKFILL MIXTURE

BACKFILL MIXTURE TO BE 1/3 SAND, 1/3 TOPSOIL, AND COMMENTS

PLANT 24" - 36" O.C.

PLANT 24" - 36" O.C.

PLANT 24" - 36" O.C.

MULCH PLANTING BEDS

- ALL PLANT MATERIAL SHALL COMPLY WITH ANSI Z60.1 "AMERICAN STANDARD FOR NURSERY STOCK". PLANT MATERIAL SHALL BE HEALTHY, VIGOROUS STOCK, GROWN WITH GOOD HORTICULTURAL PRACTICE AND INSTALLED IN ACCORDANCE WITH METHODS ESTABLISHED BY THE AMERICAN ASSOCIATION OF NURSERYMEN.
- ALL PLANTINGS AND LANDSCAPE IMPROVEMENTS SHALL BE CONSISTENT WITH THE STANDARDS OF THE CITY OF ROCHESTER HILLS PLANTING MANUAL AND LANDSCAPE REGULATION GUIDELINES.

TREE PLANTING DETAIL

NOT TO SCALE

PLANTING NOTES

PLANT MATERIAL LIST

77 CA Calamagrotis x acutiflora

WM | Weigela 'minuet'

LANDSCAPE LEGEND KEY

BOTANICAL NAME

COMMON NAME

Weigela florida 'my monet'

Weigela 'my monet'

Dwarf weigela 'minuet'

SHRUBS

QTY KEY

• PRIOR TO RELEASE OF THE PERFORMANACE BOND, THE CITY OF ROCHESTER HILLS MUST INSPECT ALL LANDSCAPE PLANTINGS.

SHRUB INSTALLATION NOT TO SCALE

CITY FILE # 21-022 SECTION # 35

BCubed for Biggby Coffee Operating Locations: Independence KY








BCubed for Biggby Coffee Operating Locations: Akron OH





Transforming communities, one project at a time.

Richards, Deanna 3175 S Rochester Road Rochester Hills, MI 48307

Hi Deanna,

Thank you for sharing interest in Meadow Valley Lawncare And Landscape LLC. As requested, below is a quote with the discussed services. If you have any questions reguarding your quote please contact us ASAP. We are looking forward to working with you!

Lets keep this short. Review the quote below. If you cannot resist our great prices go ahead and sign for agreement!

| Name/Description | Quantity | Rate | Amount | Estimate Description |
|--|----------|---------|---------|---|
| Equipment Transport and Set-up Equipment Transport and Set-up | 1 | 1000.00 | 1000.00 | Equipment Transport and Set-up |
| Equipment Equipment | 1 | 2500.00 | 2500.00 | Equipment |
| Landscape Labor Landscape Labor | 80 | 65.00 | 5200.00 | Landscape Labor |
| Plant Material Plant Material | 77 | 27.00 | 2079.00 | Plant Material-#3 Karl Forester |
| Plant Material Plant Material | 30 | 34.00 | 1020.00 | Plant Material-My monet weigela #2 |
| Plant Material Plant Material | 30 | 34.00 | 1020.00 | Plant Material-Dwarf Minuet Weigela #3 |
| Mulch-Coco Brown Mulch- Coco Brown | 40 | 75.00 | 3000.00 | Mulch- Coco Brown |
| | | | | Total \$15,819.00 |

Estimate Total \$\$15,819.00

Name

Thank you for your business!

235 Parsonage Street Saranac, MI 48881

616-443-4250 office@mvllsaranac.com

