

February 18, 2023

City of Rochester Hills 511 East Auburn Road Rochester Hills, MI 48307 Attn: Nick Watterson, ph: (248) 808-0774 HQO003484

Equipment Quotation

Pricing based on RFP-RH-20-023 Tandem Axle Truck Each major item is based on pricing submitted for RFP. City staff have determined items for build.

Install Crysteel 14' Select Dump Body including the following:

11-13 cubic yard capacity

168" length, 87" inside width, 58" front height, 36" side height, 42" rear height

Single panel, pressed-in horizontal side braces

7-gauge 201 stainless steel front, sides and rear pillars

1/4" AR450 floor

Western 10" I-beam type understructure

Air-operated tailgate

18" wide rear pillar

9-panel tailgate design constructed of 7-gauge type 201 stainless steel

Tailgate finger latches and pivot plate are stainless steel construction

8" floor-to-sides radius

10-gauge x 24" cabshield constructed of 7-gauge type 201 stainless steel

Body prop kit on each side of the frame

Install 4-hole tapered stainless steel light boxes mounted on rear pillar posts

Install chain slot holders on tailgate

Install 8" hardwood sideboards

Install side-mounted ladder, fold-down on streetside front with interior dump step

Install one (1) shovel holder & one (1) rake holder, both on streetside bulkhead

Install mudflaps in front of and behind the drive tires

Install Cougar model 3200 DC box vibrator

Bottom of the body, body hinge, body props and attaching hardware painted Black

Install Mailhot G4130-5-3 DA Telescopic Hoist including the following:

Greaseable rear hinge and replaceable rear pin

Hoist is double-acting and trunnion-mounted

Remote Grease extension kit for hoist fittings and oscillating collar

Install Roll-Rite Electric Tarp System 64000 including the following:

Aluminum tarp and tension arms with offset elbows

Aluminum tarp housing

Direct-drive motor

20ft mesh-type tarp cover

Install Central Hydraulic System including the following:

Rexroth front-mounted load-sense piston pump = A10VO100DFR

Pump is 100cc displacement

Front bolt-on crossmember for pump mounting

Spicer 1310 drive line with companion flange for easy removal

Low oil shutdown valve and override circuit



Rexroth 8m4-12 mid inlet load-sense hydraulic valve with pressure-compensated flow controls for the following functions:

EPC section for scraper up/down with load-sense limit

EPC section for scraper swing

EPC section for front plow

EPC section for front plow angle

EPC section for dump box hoist with 500 PSI A- port load sense limit

EPC section for auger

EPC section for spinner

EPC section for pre-wet

Power-beyond end cover for blade saver circuit

Blade saver hydraulic valve will be installed in the front plow lift circuit

All hoses are Parker 387 Tough cover hose

Parker SH series stainless steel hydraulic couplers for spreader circuit disconnect and plow-reverse circuit

Install Monroe 44-gallon Hydraulic Oil Reservoir/Valve Enclosure Combination unit including the following:

Type 201 stainless steel construction (mos. 00155229-B & 15570)

Mounted behind cab above frame with ship and car channel mounting brackets

Tank-mounted Zinga-type return filter

2" suction line with a 100-mesh suction strainer

Ball valve shutoff on hydraulic tank for case drain and suction ports

18" Low oil sensor mounted inside the tank

44-gallon oil capacity, filled with 35-gallon AW32 hydraulic oil

Tank is full of AW32 hydraulic oil

Sight gauge/Temperature gauge

Tank label

Stainless steel step installed on the end of the tank

Install Monroe Underbody Scraper Leg Kit and plumbing kit including the following:

Mounting hardware

Two (2) ¾" x 35" wide solid hanger plates/legs

Includes all plumbing to the scraper

Install Rexroth CS660 Electric Spreader Controller including the following:

Touch screen

Closed-loop operation for spreader, spinner and pre-wet operations

Programmable blast and pause

Data download and programming is with a thumb drive

WiFi & GPS capable to integrate with CS660 controller

Install Rexroth CS160 Electric Joystick Controller including the following:

Arm-type mounting unit or pedestal mount

6 button control includes: 1 button for pause, 1 button for hoist, 1 button for plow up/down and swing,

1 button for scraper up/down and swing, 1 button left open

Control console switches for: power float on/off, tailgate (switch-lock type), tarp in/out and low oil

override/shutdown

Low-oil and body-up indicator lights

Console to be standard size

System is laptop programmable

System also includes automatic "up-in-reverse circuit" for the scraper when chassis is in reverse

Adjustable accessory bracket for Motorola mobile radio location on console

Install Monroe QCP Loop Plow-Portion Front Hitch including the following:

Channel front bumper with steps and tapered ends



Stainless steel open grating in area between bumper and grille, over the pump

Two (2) stainless steel gripstrut stirrup steps, one on each side of bumper

Relocate front tow hooks, mounting on kicker legs

4" DA lift cylinder with Socatri rod

Pressure-release valve for plow swing mounted on streetside behind bumper

All necessary supports and braces

Includes stainless steel couplers and hoses for plow swing

Install Custom Lighting & Electrical including the following:

Utilize chassis 6 upfitter switches for the following

Truck flashers, scraper work lights & spreader work lights

Indicator lights for: low oil (red), body-up (amber) in joystick armrest

Six (6) SoundOff LED mPower (mo. EMPC2SMS4) amber/green flashers mounted in the following:

Two (2) on cabshield, front-facing

Two (2) at bottom of cabshield, one each side-facing

Two (2) at rear side facing one each side

Junction box mounted on front of the dump body for front four (4) flashers on cabshield

Four-hole tapered stainless steel light boxes mounted at rear pillar posts including:

Two (2) SoundOff LED amber flashers mounted in bottom leftside/top rightside holes

Two (2) SoundOff LED STT lights mounted in 2nd holes

Two (2) SoundOff LED backup lights mounted in 3rd holes

Two (2) SoundOff LED green flashers mounted in top leftside/bottom rightside holes

Two (2) 4" Weldex LED work lights mounted above the scraper

Two (2) 4" Weldex LED work lights mounted below the spreader assembly

LED marker lights on rear corner of dump, 3-light cluster mounted by the hinge

Maxxima LED MaxxHeat Heated Headlights (mo. MHLE-07HILO-MH)

LED Heated Plow Lights (mo. 9060) with aluminum brackets mount at 68" from base of lights to ground

Proximity switch for dump body-up light

Betts junction box mounted at the rear of the dump body

Backup alarm included

Price includes prep & paint of all non-stainless material, front bumper, frame rails as needed & dump underside. Installed pricing: \$101,135.00 ea.

HQO003485

Install Monroe 10' model MS4510 Underbody Scraper including the following:

1" thick x 20" high moldboard

 $\ensuremath{\text{\%}}$ thick hanger board with grease manifold brackets installed

2-1/2" O.D. hinge shaft

Two heavy-duty shock absorbers

Bolt-in trunnion caps for canisters; Outer arm remains bolt-on style

Two 3-1/2" x 10" actuating cylinders; Socatri rods

Cushion valve

1" solid circle with 5" center pin

Center pin is piloted into hanger board

Two 4" x 12" reversing cylinders; Socatri rods

Three hinge anchor points

Stainless Steel Hydraulic pipes for actuating cylinders

20.5" x 7" poly hold-down blocks

Parts-installation manual

Remove remote lube manifolds and grease lines in prep for Groeneveld system

Installed pricing: \$16,246.00 ea.



HQ0003486

Install Monroe model MS966-OW-GB Undertailgate Spreader including the following:

Type 201 stainless steel construction

Stainless steel anti-flow cover and spill kit included

6" auger with one-way flighting and 4" flight spacing for left-end discharge

5:1 gear box with direct-mounted motor

Application-rate sensor built into auger motor

Extended integral side plates on spreader

Spinner motor includes a seal-saver kit with grease zerk

Trough-hung self-leveling spinner with 18" poly spinner disc

Includes Schedule 40 stainless steel pipe running to rear of truck for auger, prewet, spinner and return oil

Stainless steel hydraulic disconnects with dust caps and plugs

Install Monroe Closed-Loop Pre-Wet System including the following:

One (1) 120-gallon poly pre-wet tank behind cab (measuring 36" long x 60" high x 14" wide)

Secured on the passenger side with stainless steel mounting brackets, next to hydraulic tank

 $\label{thm:continuous} \mbox{Hydraulic driven motor/pump motor with application rate sensor installed inside a poly enclosure, and \mbox{}$

mounted alongside the frame

Stainless steel piping to the rear for pre-wet liquid

Nozzle bar mounted inside the auger trough

One-way check in the pre-wet hose with a Y-type strainer

Ball valve shut-off on pre-wet tank

All weather pack connectors for electrical disconnects

Bulk fill and flusher kit included

Installed pricing: \$15,325.00 ea.

Install Groeneveld Automatic Greasing System including the following:

Groeneveld EP-0 Automatic Grease System for tandem axle chassis with standard dump body with

telescopic hoist and underbody scraper

60cc pneumatic pump in lieu of standard 42cc

Standard 4-liter reservoir

Custom fabricated pump mount bracket to fit equipment configuration

LED indicator display in cab area

Green light on when system is in pump mode

Yellow light on when low level grease switch is triggered. Will shut off pump until reservoir is refilled

Red light warning if system should have a cycle with no back pressure

Timer to accommodate light warning in lieu of standard

Pump to accommodate light warning in lieu of standard

Includes 33 total points on equipment

Includes 34 total points on chassis

All necessary plumbing, manifolds for front suspension, rear suspension, kingpins, slack adjusters, s-cams, clevis pins, tie rods, draglink, spring pins, underbody scraper, tarp bearing, dump body & telescopic hoist

Installed pricing: \$8,600.00 ea.

HQ0003487

Install Rearview Camera with Wash System including the following:

Camera system, mounted on top of light wedge, streetside

System tying into chassis wiper fluid reservoir

Chassis wiper controls for activating wash system, momentary in-cab switch for air puffer

Air puffer & washer fluid tubing

VCMS24B color camera



CEC34L1 main cable for monitor VOSHD6MNT LCD monitor mount MSF5000 stainless steel camera box VOM719WP 7" LCD color monitor

Install Rear Hitch Assembly including the following:

34" rear hitch mounting plate (no chassis STT light cutouts)

PH30 Pintle hook, multi-drill pattern – 30-ton rated height 24" to cradle

Rear tow hooks to outside of frames

D-rings for safety chains

7-way RV plug

7-way round pin plug

Remount chassis Glad Hands

Install Electric Brake Controller

Install Minimizer Floor Mats for Freightliner (mo. FKFRTL2B-MIN / 10002265)

Install Two (2) SoundOff LED mPower (mo. EMPC2SMS4) amber/green flashers mounted in chassis grille

Install the following upgrades to MS4510 Underbody Scraper including:

Install Kennametal single-insert carbide cutting edges

Install Kennametal carbide curbguards, both ends of moldboard

Install serrated step on end of moldboard, streetside Install Ray Stop moldboard savers on turntable

Paint All body underfloor, frame attachments, hoist, front hitch and rear hitch assembly Black

All stainless steel material non-painted

Installed pricing: \$6,137.00 ea. (Adds not listed in contract)

Above total installed pricing: \$147,443.00 ea. TOTAL INSTALLED PRICE FOR ONE (1) DUMP TRUCK

Chassis requirements to be confirmed prior to order entry:

CT: 135"

SCR and DPF mounted under the passenger's door

50-gallon fuel tank mounted under the driver's door

Battery box behind the cab on the left side of the frame- mount box as far rearward as possible

DEF tank mounted behind the fuel tank on left side of frame

Plow light/Headlight switch and related OEM wiring

Delete OEM front bumper

Front frame extension

Front of engine PTO provision

Stationary grille

6 dash-mounted analog switches for lighting functions

High ground clearance for scraper package

Trailer pre-wiring to rear for air & electrical brake controller

Minimum full 1-year warranty on parts and labor on all equipment.

Payment Terms: Net 30. Pricing effective for 30 days.

Pricing does not include any of the Rochester Hills RFQ discounts that may be applicable.

2% discount off total taken at invoice if payment received within 30 days.

FOB: City of Rochester Hills

Delivery: 360-420 days ARO, depending on chassis arrival

Thank you for the opportunity to quote.



Respectfully submitted by, Jon Luea/Brian Bouwman