

# ROCHESTER HILLS, MICHIGAN

## AMENDMENT TO WATER DISTRIBUTION SYSTEM STUDY

January 2005



*Infrastructure, buildings, environment, communications*

ARCADIS FPS

---

Jan M. Hauser, P.E.  
Area Manager

---

Denise Plummer, P.E.  
System Modeler

Amendment to Water  
Distribution System Study

Prepared for:  
Rochester Hills, Michigan

Prepared by:  
ARCADIS FPS, Inc.  
25200 Telegraph Road  
Southfield  
Michigan 48034  
Tel 248 936 8500  
Fax 248 936 8501

Our Ref.:  
NO000002R001  
Version 3.0

Rochester Hills City File # E01-007

Date:  
January 2005

*This document is intended only for the use of the individual or entity for which it was prepared and may contain information that is privileged, confidential, and exempt from disclosure under applicable law. Any dissemination, distribution, or copying of this document is strictly prohibited.*

Executive Summary ..... 1

Introduction ..... 2

Peaking Factors ..... 3

Modeling Analysis Results..... 3

Cost Estimates ..... 6

DWSD Coordination..... 7

DWSD Rate Analysis ..... 7

Cost Effective Analysis..... 8

Pay Back Analysis..... 8

Alternative Analysis..... 9

Conclusions ..... 9

**Appendix**

Attachment 1 – DWSD Letters

Attachment 2 –DWSD Historical Rate Calculation Tables

Attachment 3 –Pay Back Analysis

Attachment 4 – Cost Effective Analysis

## Executive Summary

The City of Rochester Hills provides drinking water to nearly 70,000 customers through approximately 22,000 connections to the publicly owned and operated water distribution system. The City purchases water on a wholesale basis from the Detroit Water and Sewerage Department (DWSD). Water is supplied through four metered connections to the DWSD water transmission system. Due to a number of factors including low and uneven pressures in the system, high peak rates required from DWSD and overall system reliability concerns after national events on September 11, 2001 and the blackout in the summer of 2003 the City commissioned a study to evaluate methods to improve the system in these areas.

The basis for the study was a hydraulic computer model of the distribution system developed using Haested Methods WaterCAD. The model simulated demands and pressures throughout the system for average day, maximum day, peak hour and fire flow conditions. The model was calibrated using hydrant flow tests under known system conditions. The model was then validated using differing sets of conditions. Results of the model follow actual system response closely.

A number of options for improving known system deficiencies were simulated including increasing flows from the existing DWSD connections, adding new pumping and storage facilities and combinations of the two. Personnel from DWSD were briefed on the approach and independently validated the model for accuracy. Recommendations for system improvements from the modeling included building two ground storage tanks and associated pumping facilities – one in the northwest of the city and one in the east central part of the City. Additionally, operational improvements were recommended to improve the efficiency of the four DWSD connections within stated DWSD requirements.

An economic analysis related to the capital costs of the recommended improvements was completed. Project costs in 2004 dollars are estimated to be approximately \$7.7 million. Reduced charges from DWSD as a result of the improvements average approximately \$1.4 million per year resulting in an estimated project payback period of about 10 years.

The results of the study strongly support building storage and pumping facilities within the City of Rochester Hills water distribution system. The alternative of maintaining the status quo is clearly not in the best interest of the long term operational, economic or reliability perspective of the system.

## Introduction

In September 2002 ARCADIS FPS, Inc. (ARCADIS) completed a water system analysis of the Rochester Hills water distribution system. The purpose of the analysis was to:

- Identify potential pressure and flow problems/deficiencies in the existing distribution system
- Identify improvements and components required to increase water pressure to the northwest portion of the City and allow for future development and,
- Identify means and methods to level out peak demand periods on the system.

The recommendations from the study included adding two finished storage water facilities – one in the northwest and one in the east central location of the City. It was also determined that an additional potential benefit of system storage would be to reduce peak flows from the Detroit Water and Sewerage Department (DWSD) connections resulting in reduced water charges. Details of the study are documented in the *Water Distribution System Modeling and Evaluation*, dated September 2002.

In October 2003 Rochester Hills contracted with ARCADIS to complete a more detailed modeling and financial analysis to confirm the results and recommendations of the original study. Management and engineering personnel from DWSD were also briefed on the project. Detailed tasks included:

1. Confirm storage tank(s) locations, size and operation.
2. Confirm project cost.
3. Meet with DWSD Engineering to gain agreement on the acceptability of water storage and the impact of storage on average day, maximum day and peak hour demands.
4. Verify DWSD contract commitments regarding adjustments to the City's current water rates as a result of reducing peak hour demands.

ARCADIS FPS

5. Obtain written documentation to the greatest extent possible from DWSD detailing the financial implications the reduced peaking factors will have on water rates.
6. Develop cost effective analysis and pay-back estimates.

This report should be considered an addendum and intergral to the original report.

### **Peaking Factors**

Peaking factors are used throughout the report and refer to the relationship between average day, maximum day and peak hour demands. These factors are calculated by dividing the maximum day and peak hour demand by the annual average day demand. Peaking factors are used to size facilities during the design process but are also used by DWSD to set contract community rates. While they refer to that same theoretical calculations they are used in different ways.

Peaking factors are used during the modeling analysis as design criteria to size facilities such as pump stations. For this analysis DWSD required peaking factors of 3 for maximum day and 5 for peak hour, respectively. These hypothetical peaking factors are higher than actual historical recorded peaking factors resulting in a conservative design of facilities.

The other use of peaking factors is in the estimate of DWSD annual charges to the City. These peaking factors are determined from actual annual water demands registered by the master meters at the four connection points with the DWSD system. Average day demand is calculated by dividing the sum of all four meters over the entire year by 365. The maximum day demand is determined by the actual 24-hour maximum demand during the year. The peak hour is determined in the same way based on the actual highest recorded single hour throughout the year. The peaking factors are determined by dividing the maximum day and peak hour usage by the annual average day demand to arrive at the maximum day peak and peak hour factors, respectively. These factors vary from year to year.

### **Modeling Analysis Results**

Additional modeling analysis was performed to determine if demands from the four DWSD supply points could be equalized and also to determine the most beneficial

location, capacity, and control strategy for the proposed water tanks and booster pumping stations.

During the course of this additional modeling, ARCADIS met with Ali Ghanavi from DWSD on several occasions to discuss specific aspects of the model and the project input to ensure their acceptance in the concept of water storage for Rochester Hills.

DWSD required an increase in the theoretical peaking factors to determine the maximum day demand and peak hour demand from what was used during the original study. The increase in the peaking factor and subsequent demands are shown in Table 1.

Table 1				
	Previous Peak Factor (2002/2003 Rates)	Previous Demand (MGD)	Current Peak Factor	Current Demand (MGD)
Max Day	2.4	19.1	3	25
Peak Hour	3.4	27.1	5	40

The demand information DWSD provided for Rochester Hills also changed the supply point distribution. The redistribution of the flow percentages from each DWSD connection is shown in Table 2. Approximately 40% of the demand is located in the north and 60% is located in the south.

Table 2		
	<i>Supply Point Distribution</i>	
	Previous	Current
RC-1	19%	36%
RC-2	62%	41%
RC-3	15%	21%
RC-4	4%	2%

Modeling results indicate that due to the higher maximum day demand the tank located in the east central part of the City should be increased to 3.0 million gallons (MG) from 2.0 MG that was previously proposed. The proposed location for the east central tank is north of Avon Road and east of Rochester Road.

ARCADIS FPS

The original recommendation of a 2.0 MG storage tank in the north is still adequate. The proposed location for the tank and associated booster pumping station in the north is on Tienken Road west of Adams Road.

The preliminary capacity of the booster pumps was determined using the model. They were sized to restrict flow from the DWSD supply points to the maximum daily demand. The preliminary pump capacity in the north is approximately 6000 gpm at 150 feet TDH. The preliminary pump capacity in the south is approximately 7000 gpm at 145 feet TDH. Final pump capacities will be determined during detailed design.

DWSD evaluated the possible impact of the proposed new Rochester Hills storage facilities on their system. Specifically, they were concerned about the impact of the proposed tank in the north because of its close proximity to RC-2. The minimum hydraulic grade line (HG) for DWSD's system at RC-2 is 1120 feet. The booster station in the north maintains the hydraulic grade at RC-2 at 1137 feet.

To maintain demands on the DWSD supply points at the maximum day demand under worst case conditions flow control valves are required at each feed point. These valves can be remotely monitored through the City's SCADA system.

Extended period model simulations (24-hours) were run to ensure the new storage tanks would drain and fill adequately with DWSD demands limited to the maximum daily demand. The control logic for the booster pumps was discussed with DWSD. For each booster pumping station a control node was chosen to determine the pump status. Each tank had a fill line and a drain line that acted as the suction for the pumping station. The fill line had a valve that was set to close any time the pump was on.

The control junction in the north was located at node J-630 on the suction side of the booster pumping station. Pump control strategy included turning the pumps on if the HGL at the control node fell below 1000 feet and the tank level was over 34 feet. Once the tank level dropped below 11.5 feet the pump turned off.

The control junction in the south was located adjacent to supply feed RC-1. If the HGL at the control node was below 1000 feet (meaning the system was trying to draw more water and the demand was higher) and the tank level was over 34 feet, the pump turned on. Once the tank level dropped below 11.5 feet the pump turned off.



In order for the booster pump station to “back feed” areas in the north several existing flow control valves (FCV) need to be deactivated. FCV 6 located on Rosebriar south of Rain Tree, FCV 8 located on Brewster, and FCV 21 located on Medinah all need to be deactivated. When FCV 21 was deactivated the water was recirculating to feed the booster pumping station. Therefore, check valves were added in the model on Palm Aire.

**Cost Estimates**

Project cost estimates were updated based on the new recommendations noted above. Total project costs are detailed in Table 3. Because of the early stage of planning probable construction cost estimates include a 20 percent construction contingency and 20 percent engineering allowance for design, construction engineering and administration. Estimate of probable project costs is \$7.7 million.

Table 3 Estimate of Probable Costs		
Items	Quantities	Amount
Prestressed Concrete Ground Level Tank		
3.0 MG	Lump Sum	\$1,300,000.00
2.0 MG	Lump Sum	\$1,060,000.00
Flow Control Valves, Meters and Chambers		
RC-1, 16"	Lump Sum	\$50,000.00
RC-2, 30"	Lump Sum	\$90,000.00
RC-3, 54"	Lump Sum	\$160,000.00
RC-4, 30"	Lump Sum	\$90,000.00
North Tank, 2 pumps (6000 gpm @150')	Lump Sum	\$1,300,000.00
South Tank, 2 pumps (7000 gpm @145')	Lump Sum	\$1,300,000.00
	Subtotal	\$5,350,000.00
	Contingencies	\$1,050,000.00
	Total Construction Cost	\$6,400,000.00
	Engineering	\$1,300,000.00
	Total Project Cost	\$7,700,000.00

### DWSD Coordination

ARCADIS personnel met numerous times to discuss the project with DWSD personnel from both a technical and management viewpoint. DWSD performed independent model analysis using the hydraulic model previously developed by ARCADIS. The new tanks were included in the model. DWSD was satisfied that the impact on the existing DWSD transmission system is acceptable. A letter signed by the Assistant Director of Engineering Services conceptually agreeing to the new storage facilities was received on July 26, 2004, and is attached.

ARCADIS also met with management personnel to determine the current process to determine new rates. DWSD agreed that after the new facilities are constructed and in operation new peaking factors will be determined. A letter signed by the Director of DWSD and received on May 27, 2004, details the procedure and is attached.

### DWSD Rate Analysis

The DWSD customer community rate determination is based on a complex equation that takes into account the annual average day demand, maximum day demand, peak hour demand, distance from DWSD facilities and elevation. The only variable that can be manipulated through system design and operation is the peak hour demand. System storage can be used during peak demand periods to subsidize required flows from DWSD, effectively limiting the flow requirements from DWSD to maximum day demand. This in turn reduces one of the five factors – peak hour peaking factor- to the maximum day peak factor reducing the overall rate charged to Rochester Hills by DWSD.

It is estimated using the 2004/2005 rate calculation for Rochester Hills supplied by DWSD that the recommended improvements will reduce the overall rate for wholesale water from DWSD from \$15.60/McF to \$12.75/McF. This calculation is shown in the tables labeled DWSD Rate Calculation – 2005 and DWSD Rate Calculation – 2005 Modified in the Appendix. The only difference in the calculation is the reduction of the Peak Hour Peaking Factor from 3.2 to 2.5. Based on current maximum day demand in Rochester Hills this results in an estimated annual savings of \$1,187,281. This savings will vary from year to year based on total consumption and maximum day flows but will always be less than the cost without the new storage facilities based on the existing DWSD rate structure.

### Cost Effective Analysis

A cost effective analysis was conducted to determine the most cost effective approach for the two options – continuing the current operation of the Rochester Hills water system or adding storage that will reduce peak flows to maximum day flows. The analyses calculated Average Equivalent Annual Cost (AEAC) for both systems. The AEAC is an industry standard for comparing options and results in an annual cost to fund each option. Calculations are attached in the Appendix.

The analysis takes into account the cost of purchasing water from DWSD and the cost to pay back bonds for any associated capital improvements. Year 2005 was used as the baseline year for the capital improvements with 20 years to pay back the bonds at an annual interest rate of 5%. Results of the analysis show that the storage option is the most cost effective. AEAC for the storage option is \$5,969,688 and \$6,485,098 for the status quo option.

Note that the AEAC for status quo option equals the estimated charges from DWSD for the year 2005. This is because there is no capital costs associated with this option leaving only water charges to pay off.

### Pay Back Analysis

Payback analysis was completed by dividing total project costs by the net annual profit. The estimated total project costs are detailed above and are equal to \$7,700,000. The net annual profit is determined by the estimated amount of rate reduction as a result of the improvements minus estimated operation and maintenance cost and financing costs of the new facilities.

The DWSD rate reduction was estimated by evaluating system demands and associated costs for the years 2001 through 2004. The highest annual savings was \$1.7 million in 2001, the lowest of \$1.2 million was in 2004. The average cost savings with the addition of storage was approximately \$1.4 million per year.

Operation and maintenance costs were estimated using professional experience and data from similar systems for salaries and administrative costs, electricity, chemicals and repair and maintenance. It is noted that these types of facilities are highly automated and require nominal personal attention during normal operation. For this analysis it was estimated approximately 14 person hours per week are required over the

ARCADIS FPS

life of the facility. This conservative estimate could easily be handled by existing personnel. Average annual O&M costs were estimated to be approximately \$124,000.

Annual costs associated with financing the capital costs were estimated using 4.5% interest rate amortized over 20 years. The estimated annual payment is slightly over \$550,000. This assumes a portion of the project development costs will be funded through existing reserves.

Using these figures the pay-back period is estimated to be approximately 10 years.

### Alternative Analysis

The following table provides a side by side comparison of the two potential choices of building new storage and pumping facilities or continuing to operate the system in the current configuration.

	Pros	Con
Storage	<ul style="list-style-type: none"> <li>■ Improved reliability</li> <li>■ Improved system pressures</li> <li>■ Improved fire fighting capability</li> <li>■ Economically advantageous</li> <li>■ Good system design</li> </ul>	<ul style="list-style-type: none"> <li>■ DWSD uncertainty</li> <li>■ DWSD customer uncertainty</li> <li>■ Upfront investment</li> </ul>
No Storage	<ul style="list-style-type: none"> <li>■ Known system response</li> <li>■ Known rate impacts</li> <li>■ Easy</li> <li>■ No capital investment required</li> </ul>	<ul style="list-style-type: none"> <li>■ System issues not addressed</li> <li>■ Not economically beneficial</li> <li>■ Potential adverse financial impacts due to other customers building storage</li> </ul>

### Conclusions

A detailed technical and economic evaluation was conducted on the validity of adding system storage to the Rochester Hills water system. The following conclusions have been reached:

- The addition of storage to the Rochester Hills water system is both technically and economically desirable.
- With the current information on DWSD rate structure and opinions of probable project costs the pay-back period is approximately 10 years after the improvements are in operation.

- The required storage should be ground storage with booster pump stations. A 2.0 MG tank is required in the northwest and a 3.0 MG tank is required in the east central.
- The addition of storage will allow peak water demands required from DWSD to be reduced to maximum day demands resulting in lower future fees from DWSD.
- The addition of storage will solve the concerns detailed in the original study – to improve pressures in the northwest portion of the system, level out peak demands from DWSD and improve flow and pressure problems throughout the system.
- Overall, the improvements will increase reliability and flexibility of the existing system.

# **Attachment 1**

CITY OF DETROIT  
WATER & SEWER DEPARTMENT  
GENERAL ADMINISTRATION

715 RANDOLPH STREET  
DETROIT, MICHIGAN 48226-28  
PHONE 313-224-4800/224-686  
FAX 313-224-6067

July 26, 2004

Mr. Roger H. Rouse  
Director of Public Services  
City of Rochester Hills  
1000 Rochester Hills Drive  
Rochester Hills, Michigan 48309-3034

RECEIVED  
JUL 28 2004  
ARCADIS FPS

Regarding Two (2) Proposed Water Storage Facilities

Dear Mr. Rouse:


This is in response to the preliminary hydraulic analysis about the above subject, submitted by your consultant (ARCADIS/FPS) to our Planning Section dated April 5, 2004. The Detroit Water and Sewerage Department (DWSD) conceptually approves the proposed Storage Facilities as described below, under the following conditions.

1. A 2.0 MG ground reservoir and the associated pumping station on Walton Road west of Adams Road. The operation of this facility will be restricted to a maximum flow of 9000 gpm and/or minimum HGL of 1120 ft (USGS) at the City of Rochester Hills Master Meter RC-2 located on Walton Road east of Squirrel Road. Proper design provisions will need to be incorporated in the design of this facility to accommodate this restriction.
2. A 3.0 MG ground reservoir and the associated pumping station on Avon Road east of North Rochester Road. The operation of this facility will be restricted to a maximum flow of 4000 gpm at the City of Rochester Hills Master Meter RC-4 located on 24 Mile Road and Dequindre Road. Proper design provisions will need to be incorporated in the design of this facility to accommodate this restriction.

Please be advised that since the proposed facilities will be part of the City of Rochester Hills system, DWSD's review of the subject hydraulic analysis, only pertains to the impact of the proposed facilities on DWSD's system. The possible impact of the proposed facilities on the City of Rochester Hills system and its Peaking Factors was not the focus of DWSD's review.

If you have any questions or need additional information, please contact Mr. Ali Ghanavi of my staff at 313.964.9873.

Sincerely,



Gregory B. White, P.E.  
Assistant Director of Engineering Services

GBW/BD/dj

cc: Mr. Jan Hauser, P.E. (ARCADIS/FPS)

Attachment 1

KWAHE M. KILNTRICK, Mayor



CITY OF DETROIT  
WATER AND SEWERAGE DEPARTMENT  
GENERAL ADMINISTRATION

735 RANDOLPH STREET  
DETROIT, MICHIGAN 48226-2830  
PHONE 313-224-6800/224-4801  
FAX 313-224-6067

May 27, 2004

Mr. Roger H. Rousse  
City of Rochester Hills  
1000 Rochester Hills Drive  
Rochester Hills, Michigan 48309

Dear Mr. Rousse:


RE: Implementation of Peaking Factors with the Addition of Internal Storage

In response to your request, the Detroit Water and Sewerage Department (DWSD) will implement peaking factors in the order described below for a wholesale water customer adding storage.

Once a wholesale customer adds storage to its system with the intention of reducing peaking factors, a new peaking factor adjustment period will begin in the following sequence:

1. The customer will inform the Department that the facilities are completed and in operation.
2. The first peak season following the start of operations, DWSD will determine peaks based on recorded flows to the customer in the same manner as the rest of the wholesale customer base.
3. These peaks will be the first data point in new peaking factor calculations. All prior peaking information will be excluded from future peak calculations.
4. This peaking information shall be used for rate setting purposes on a going forward basis only. The Department will not adjust past or existing rates based on the new peaking information.
5. Peaking information collected for future years will be incorporated with the initial peaking information in the same manner applied to all other wholesale customers. Therefore, once the customer has obtained enough annual peak data points, the customer's peaking factors will be calculated with the historical same data set as all other customers.

If you need any further assistance, please contact my office at 313-224-4701.

Sincerely yours,  
  
Victor M. Mercado  
Director

VMM:RC/rjc

cc: Gary Fujita, DWSD  
James George, DWSD  
Greg White, DWSD  
Robert Walter, Law Department  
Laurie Hohwart, Law Department

Attachment 1



# **Attachment 2**

Historical DWSD Rate Summary

Year	Base	Modified	Savings
2004	\$6,485,098	\$5,297,817	\$1,187,281
2003	\$6,389,087	\$5,097,444	\$1,291,644
2002	\$6,229,519	\$4,689,358	\$1,540,161
2001	\$5,921,350	\$4,351,959	\$1,569,390

\$1,397,119

Base = without the additiona of storage and pumping facilities

Modified = with the addition of storage and pumping facilities

ARCADIS FPS

**2004 Revenue Requirement Without Storage**

Service Category	Peaking Factors	of Service	Applied Units	Unit Cost	Allocated Costs
Base (Mcf/Day)		1138.6	1238.1	\$ 840.25	\$1,040,314
Max. Day	2.5	2846.5	1707.9	\$ 467.80	\$ 798,956
Peak Hour	3.2	3643.5	797.0	\$ 194.21	\$ 154,789
Base Distance		26.9	33304.9	\$ 16.83	\$ 560,521
Max Day Distance			45942.5	\$ 13.09	\$ 601,387
Peak Hour Distance			21439.8	\$ 13.09	\$ 280,647
Base Distance/Elevation		48.7	60295.5	\$ 10.36	\$ 624,661
Max. Day Distance/Elevation			83174.7	\$ 19.37	\$1,611,095
Peak Hour Distance/Elevation			38814.9	\$ 19.37	\$ 751,844
Customer A (Commercial)		108		\$ 9.67	\$ 1,044
Customer B (Meters)		2385		\$ 25.09	\$ 59,840
<b>Total FY Revenue Requirement</b>					<b>\$6,485,098</b>
FY2004 Volume		415589			
FY Rate					\$15.60 /Mcf

ARCADIS FPS

**2004 Revenue Requirement With Storage**

Service Category	Peaking Factors	Units of Service	Applied Units	Unit Cost	Allocated Costs
Base (Mcf/Day)		1138.6	1238.1	\$ 840.25	\$ 1,040,314
Max. Day	2.5	2846.5	1707.9	\$ 467.80	\$ 798,956
Peak Hour	2.5	2846.5	0	\$ 194.21	\$ -
Base Distance		26.9	33304.9	\$ 16.83	\$ 560,521
Max Day Distance			45942.5	\$ 13.09	\$ 601,387
Peak Hour Distance			0	\$ 13.09	\$ -
Base Distance/Elevation		48.7	60295.5	\$ 10.36	\$ 624,661
Max. Day Distance/Elevation			83174.7	\$ 19.37	\$ 1,611,095
Peak Hour Distance/Elevation			0	\$ 19.37	\$ -
Customer A (Commercial)		108		\$ 9.67	\$ 1,044
Customer B (Meters)		2385		\$ 25.09	\$ 59,840
<b>Total FY Revenue Requirement</b>					<b>\$ 5,297,817</b>
FY2004 Volume		415589			
FY Rate					\$12.75 /Mcf

ARCADIS FPS

**2003 Revenue Requirement Without Storage**

Service Category	Peaking Factors	Units of Service	Applied Units	Unit Cost	Allocated Costs
Base (Mcf/Day)		1164.4	1266.8	\$ 759.92	\$ 962,667
Max. Day	2.5	2911.0	1746.6	\$ 395.66	\$ 691,060
Peak Hour	3.3	3842.5	931.5	\$ 88.49	\$ 82,430
Base Distance		27.7	35090.4	\$ 15.20	\$ 533,373
Max Day Distance			48380.8	\$ 11.60	\$ 561,218
Peak Hour Distance			25803.1	\$ 11.60	\$ 299,316
Base Distance/Elevation		51.6	65366.9	\$ 8.65	\$ 565,424
Max. Day Distance/Elevation			90124.6	\$ 18.93	\$ 1,706,058
Peak Hour Distance/Elevation			48066.4	\$ 18.93	\$ 909,898
Customer A (Commercial)		96		\$ 11.30	\$ 1,085
Customer B (Meters)		3480		\$ 22.00	\$ 76,560
<b>Total FY Revenue Requirement</b>					<b>\$6,389,087</b>
FY2003 Volume		425006			
FY Rate					\$15.03 /Mcf

ARCADIS FPS

**2003 Revenue Requirement With Storage**

Service Category	Peaking Factors	Units of Service	Applied Units	Unit Cost	Allocated Costs
Base (Mcf/Day)		1164.4	1266.8	\$ 759.92	\$ 962,667
Max. Day	2.5	2911.0	1746.6	\$ 395.66	\$ 691,060
Peak Hour	2.5	2911.0	0.0	\$ 88.49	\$ -
Base Distance		27.7	35090.4	\$ 15.20	\$ 533,373
Max Day Distance			48380.8	\$ 11.60	\$ 561,218
Peak Hour Distance			0.0	\$ 11.60	\$ -
Base Distance/Elevation		51.6	65366.9	\$ 8.65	\$ 565,424
Max. Day Distance/Elevation			90124.6	\$ 18.93	\$ 1,706,058
Peak Hour Distance/Elevation			0.0	\$ 18.93	\$ -
Customer A (Commercial)		96		\$ 11.30	\$ 1,085
Customer B (Meters)		3480		\$ 22.00	\$ 76,560
<b>Total FY Revenue Requirement</b>					<b>\$ 5,097,444</b>
FY2003 Volume		425006			
FY Rate					\$11.99 /Mcf

ARCADIS FPS

**2002 Revenue Requirement Without Storage**

Service Category	Peaking Factors	Units of Service	Applied Units	Unit Cost	Allocated Costs
Base (Mcf/Day)		1232.9	1349.3	\$ 686.98	\$ 926,942
Max. Day	2.4	2959.0	1726.06	\$ 370.51	\$ 639,522
Peak Hour	3.4	4191.9	1232.9	\$ 92.27	\$ 113,760
Base Distance		27.7	37375.6	\$ 13.90	\$ 519,521
Max Day Distance			47811.9	\$ 10.36	\$ 495,331
Peak Hour Distance			34151.3	\$ 10.36	\$ 353,808
Base Distance/Elevation		51.6	69623.9	\$ 7.69	\$ 535,408
Max. Day Distance/Elevation			89064.7	\$ 16.86	\$1,501,631
Peak Hour Distance/Elevation			63617.6	\$ 16.86	\$1,072,593
Customer A (Commercial)		96		\$ 10.27	\$ 986
Customer B (Meters)		3480		\$ 20.12	\$ 70,018
<b>Total FY Revenue Requirement</b>					<b>\$6,229,519</b>
FY2002 Volume		450009			
FY Rate					\$13.84 /Mcf

ARCADIS FPS

**2002 Revenue Requirement With Storage**

Service Category	Peaking Factors	Units of Service	Applied Units	Unit Cost	Allocated Costs
Base (Mcf/Day)		1232.9	1349.3	\$ 686.98	\$ 926,942
Max. Day	2.4	2959.0	1726.06	\$ 370.51	\$ 639,522
Peak Hour	2.4	2959.0	0.0	\$ 92.27	\$ -
Base Distance		27.7	37375.6	\$ 13.90	\$ 519,521
Max Day Distance			47811.9	\$ 10.36	\$ 495,331
Peak Hour Distance			0.0	\$ 10.36	\$ -
Base Distance/Elevation		51.6	69623.9	\$ 7.69	\$ 535,408
Max. Day Distance/Elevation			89064.7	\$ 16.86	\$ 1,501,631
Peak Hour Distance/Elevation			0.0	\$ 16.86	\$ -
Customer A (Commercial)		96		\$ 10.27	\$ 986
Customer B (Meters)		3480		\$ 20.12	\$ 70,018
<b>Total FY Revenue Requirement</b>					<b>\$4,689,358</b>
FY2002 Volume		450009			
FY Rate					\$10.42 /Mcf



ARCADIS FPS

**2001 Revenue Requirement Without Storage**

Service Category	Peaking Factors	Units of Service	Applied Units	Unit Cost	Allocated Costs
Base (Mcf/Day)		1340.5	1478.1	\$ 574.58	\$ 849,287
Max. Day	2.4	3217.2	1876.7	\$ 293.73	\$ 551,243
Peak Hour	3.4	4557.7	1340.5	\$ 176.65	\$ 236,799
Base Distance		27.7	40943.37	\$ 12.02	\$ 492,139
Max Day Distance			51984.59	\$ 8.84	\$ 459,544
Peak Hour Distance			37131.85	\$ 8.84	\$ 328,246
Base Distance/Elevation		51.6	76269.96	\$ 6.89	\$ 525,500
Max. Day Distance/Elevation			96837.72	\$ 14.52	\$ 1,406,084
Peak Hour Distance/Elevation			69169.8	\$ 14.52	\$ 1,004,345
Customer A (Commercial)		96		\$ 9.68	\$ 929
Customer B (Meters)		3480		\$ 19.32	\$ 67,234
<b>Total FY Revenue Requirement</b>					<b>\$5,921,350</b>
FY2001 Volume		489283			
FY Rate					\$12.10 /Mcf

ARCADIS FPS

**2001 Revenue Requirement With Storage**

Service Category	Peaking Factors	Units of Service	Applied Units	Unit Cost	Allocated Costs
Base (Mcf/Day)		1340.5	1478.1	\$ 574.58	\$ 849,287
Max. Day	2.4	3217.2	1876.7	\$ 293.73	\$ 551,243
Peak Hour	2.4	3217.2	0	\$ 176.65	\$ -
Base Distance		27.7	40943.37	\$ 12.02	\$ 492,139
Max Day Distance			51984.59	\$ 8.84	\$ 459,544
Peak Hour Distance			0	\$ 8.84	\$ -
Base Distance/Elevation		51.6	76269.96	\$ 6.89	\$ 525,500
Max. Day Distance/Elevation			96837.72	\$ 14.52	\$ 1,406,084
Peak Hour Distance/Elevation			0	\$ 14.52	\$ -
Customer A (Commercial)		96		\$ 9.68	\$ 929
Customer B (Meters)		3480		\$ 19.32	\$ 67,234
<b>Total FY Revenue Requirement</b>					<b>\$4,351,959</b>
<b>FY2001 Volume</b>		<b>489283</b>			
<b>FY Rate</b>					<b>\$8.89 /Mcf</b>

# **Attachment 3**

# ARCADIS FPS

## Pay-Back Analysis

Estimated Total Project Cost		\$7,700,000
Estimated Rate Savings	Max	\$1,569,390
	Min	\$1,187,281
	Ave	\$1,397,119
O&M	Max	\$174,000
	Min	\$74,000
	Ave	\$124,000
Debt payment	Max(7.7 @5)	\$613,000
	Min (6.4 @ 4.5)	\$490,000
	Ave	\$551,500
Pay-Back Period (years)		10.7

# **Attachment 4**

**COST EFFECTIVE ANALYSIS - DATA INPUT**

Project Name: City of Rochester Hills

Alternative Name: No Storage

Planning Period in years: 20  
 Initial Year of Planning Period: 2005  
 Construction Period, in years: 0.0

Interest Rate %: 5.00

Structures Value, year 0: \$0

Process Equipment

20 yr. Equipment Value, year 0: \$0  
 15 yr. Equipment Value, year 0:

Auxiliary Equipment

15 yr. Equipment Value, year 0: \$0  
 10 yr. Equipment Value, year 0:

Land Cost: \$0  
 Total Construction Cost: \$0  
 Contingences, % : 0.00  
 Technical Services, % : 0.00

Salaries & Administrative Cost, year 2005 \$0  
 year 2025 \$0

Power & Gas? type Y, just Power? type P: P

Power Cost, year 2005 \$0  
 year 2025 \$0

Chemical Cost, year 2005 \$0  
 year 2025 \$0

Repair & Maintenance Cost, year 2005 \$0  
 year 2025 \$0

Rate Calculation year 2005 \$6,485,098  
 year 2025 \$6,485,098

ARCADIS FPS

City of Rochester Hills

No Storage

ESTIMATE OF OPERATION AND MAINTENANCE COST

	<u>2005</u>	<u>2025</u>
Salaries & Administrative	\$0	\$0
Power	0	0
Chemicals	0	0
Repair & Maintenance	0	0
Rate Calculation	6,485,098	6,485,098
	<hr/>	<hr/>
TOTAL O&M COSTS	\$6,485,098	\$6,485,098
TOTAL FIXED O&M	6,485,098	6,485,098
TOTAL VARIABLE O&M	\$0	\$0
Yearly Increase		\$0
		5

No Storage

**REPLACEMENT COST AND SALVAGE COST SUMMARY**

	Initial Cost at <u>Year 0</u>	Replacement Cost at <u>Year 10</u>	Replacement Cost at <u>Year 15</u>	Salvage Value <u>Year 20</u>
A. Structures				
50 year life	\$0			
Salvage Value				\$0
B. Process Equipment				
20 year life	0			
15 year life	0			
Replacement Cost			0	
Salvage Value				0
C. Auxiliary Equipment				
15 year life	0			
10 year life	0			
Replacement Cost		0	0	
Salvage Value				0
D. Other Costs		5		
Contingencies	0			
Technical Services	0			
Land	0			0
	<hr/>			
TOTAL PROJECT COST	\$0			
TOTAL REPLACEMENT COST		\$0	\$0	
TOTAL SALVAGE VALUE				\$0



No Storage

**AVERAGE EQUIVALENT ANNUAL COST DETERMINATION**

**COST AND OTHER DATA UTILIZED**

Planning Period: 20 Years			
Initial Cost of Project:	\$0	Construction Period:	0.0 Year
Replacement Cost at Year 10:			\$0
Replacement Cost at Year 15:			\$0
Salvage Value at Year 20:			
Structures	-		\$0
Process Equipment	-		0
Auxiliary Equipment	-		0
Land	-		0
Total	-		\$0
Constant Annual Operation & Maintenance Cost:			\$6,485,098
Variable Annual Operation & Maintenance Cost:			\$0 Year 0 to \$0 Year 20
Interest Rate:	5 %		

**DETERMINE PRESENT WORTH & AVERAGE EQUIVALENT ANNUAL COST OF THIS PLAN OVER 20 YEARS**

Factors: ( 20 years at 5 %, unless noted)		
Present worth (PW) of constant annual O&M cost:		12.4622
PW of variable annual O&M cost (annual increase):		98.4884
Present worth of replacement cost - Year 10:	5	0.6139
Present worth of replacement cost - Year 15:		0.4810
Present worth of salvage value:		0.3769
Interest during construction = Initial cost x (0.5) x Period of Construction (Years) x Interest rate.		
Equivalent annual cost = Total present worth x		0.0802

**CALCULATIONS - PRESENT WORTH**

1. Initial Cost		\$0
2a. Constant O&M		80,818,655
2b. Variable O&M		0
3. Replacement Cost		0
4. Salvage Value	(minus)	0
5. Interest During Construction		0
6. Total Present Worth		<u>\$80,818,655</u>

**AVERAGE EQUIVALENT ANNUAL COST**

<u>\$80,818,655</u>	x	0.0802	<b>\$6,485,098</b>
---------------------	---	--------	--------------------

**COST EFFECTIVE ANALYSIS - DATA INPUT**

Project Name: City of Rochester Hills

Alternative Name: Water Storage Alternatives

Planning Period in years: 20  
 Initial Year of Planning Period: 2005  
 Construction Period, in years: 0.8

Interest Rate %: 5.00

Structures Value, year 0: \$4,400,000

Process Equipment

20 yr. Equipment Value, year 0: \$650,000  
 15 yr. Equipment Value, year 0:

Auxiliary Equipment

15 yr. Equipment Value, year 0: \$300,000  
 10 yr. Equipment Value, year 0:

Land Cost: \$0  
 Total Construction Cost: \$5,350,000  
 Contingences, % : 20.00  
 Technical Services, % : 25.00

Salaries & Administrative Cost, year 2005 \$15,000  
 year 2025 \$15,000

Power & Gas? type Y, just Power? type P: P  
 Power Cost, year 2005 \$46,000  
 year 2025 \$46,000

Chemical Cost, year 2005 \$10,000  
 year 2025 \$10,000

Repair & Maintenance Cost, year 2005 \$2,500  
 year 2025 \$100,000

rate calculation year 2005 \$5,297,817  
 year 2025 \$5,297,817

ARCADIS FPS

City of Rochester Hills

Water Storage Alternatives

**ESTIMATE OF OPERATION AND MAINTENANCE COST**

	<u>2005</u>	<u>2025</u>
Salaries & Administrative	\$15,000	\$15,000
Power	46,000	46,000
Chemicals	10,000	10,000
Repair & Maintenance	2,500	100,000
rate calculation	5,297,817	5,297,817
	<hr/>	<hr/>
TOTAL O&M COSTS	\$5,371,317	\$5,468,817
TOTAL FIXED O&M	5,371,317	5,371,317
TOTAL VARIABLE O&M	\$0	\$97,500
Yearly Increase		\$4,875

ARCADIS FPS

City of Rochester Hills

Water Storage Alternatives

**REPLACEMENT COST AND SALVAGE COST SUMMARY**

	Initial Cost at <u>Year 0</u>	Replacement Cost at <u>Year 10</u>	Replacement Cost at <u>Year 15</u>	Salvage Value <u>Year 20</u>
A. Structures				
50 year life	#####			
Salvage Value				\$2,640,000
B. Process Equipment				
20 year life	650,000			
15 year life	0			
Replacement Cost			0	
Salvage Value				0
C. Auxiliary Equipment				
15 year life	300,000			
10 year life	0			
Replacement Cost		0	300,000	
Salvage Value				200,000
D. Other Costs				
Contingencies	1,070,000			
Technical Services	1,337,500			
Land	0			
	-----	-----	-----	-----
TOTAL PROJECT COST	#####			
TOTAL REPLACEMENT COST		\$0	\$300,000	
TOTAL SALVAGE VALUE				\$2,840,000

**AVERAGE EQUIVALENT ANNUAL COST DETERMINATION**

**COST AND OTHER DATA UTILIZED**

Planning Period: 20 Years		
Initial Cost of Project:	#####	Construction Period: 0.8 Year
Replacement Cost at Year 10:		\$0
Replacement Cost at Year 15:		\$300,000
Salvage Value at Year 20:		
Structures	-	\$2,640,000
Process Equipment	-	0
Auxiliary Equipment	-	200,000
Land	-	0
Total	-	<u>\$2,840,000</u>
Constant Annual Operation & Maintenance Cost:		\$5,371,317
Variable Annual Operation & Maintenance Cost:		\$0 Year 0 to
		\$97,500 Year 20
Interest Rate:	5 %	

**DETERMINE PRESENT WORTH & AVERAGE EQUIVALENT ANNUAL COST OF THIS PLAN OVER 20 YEARS**

Factors: ( 20 years at 5 %, unless noted)	
Present worth (PW) of constant annual O&M cost:	12.4622
PW of variable annual O&M cost (annual increase):	98.4884
Present worth of replacement cost - Year 10:	0.6139
Present worth of replacement cost - Year 15:	0.4810
Present worth of salvage value:	0.3769
Interest during construction = Initial cost x (0.5) x Period of Construction (Years) x Interest rate.	
Equivalent annual cost = Total present worth x	0.0802

**CALCULATIONS - PRESENT WORTH**

1. Initial Cost		\$7,757,500
2a. Constant O&M		66,938,482
2b. Variable O&M		480,131
3. Replacement Cost		144,305
4. Salvage Value	(minus)	1,070,366
5. Interest During Construction		145,453
6. Total Present Worth		<u>\$74,395,505</u>

**AVERAGE EQUIVALENT ANNUAL COST**

\$74,395,505	x	0.0802	<b>\$5,969,688</b>
--------------	---	--------	--------------------